

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES													TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
FULL C.E. ITEMS	TRAINING	ROADWAY	EROSION CONTROL	CHANNEL	ABUTMENT No. 1	PIER	ABUTMENT No. 2	APPROACH SLAB No. 1	APPROACH SLAB No. 2	DECK	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS	
		3											3		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10				
		42											42		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH (MOD.)	618.10				
		2											2		SY	DETECTABLE WARNING SURFACE	618.30				
		600											600		LF	SNOW FENCE (MOD. - PDF)	620.70				
		2											2		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
		282											282		LF	ALUMINUM APPROACH RAILING	621.74				
		175											175		LF	REMOVL AND DISP OF GUARD RAIL	621.80				
		60											60		LF	TEMPORARY TRAFFIC BARRIER	621.90				
1													1		LS	FIELD OFFICE - ENGINEERS	631.10				
1													1		LS	TESTING EQUIPMENT - CONCRETE	631.16				
1													1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17				
1													1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25				
		520											520		HR	EMPLOYEE TRAINEESHIP	634.10				
		1											1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
		1											1		LS	TRAFFIC CONTROL	641.10				
		1400											1400		LF	DURABLE 4" YELLOW LINE (THERMOPLASTIC)	646.41				
		22											22		LF	TEMPORARY 24" STOP BAR (PAINT)	646.66				
													900		SY	GEOTEXTILE UNDER STONE FILL	649.31				
													330		SY	GEOTEXTILE FOR SILT FENCE	649.51				
													370		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
													40		LB	SEED	651.15				
													40		LB	SEED-WINTER RYE	651.17				
													300		LB	FERTILIZER	651.18				
													2		TON	AGRICULTURAL LIMESTONE	651.20				
													2		TON	HAY MULCH	651.25				
													280		CY	TOPSOIL	651.35				
													550		SY	GRUBBING MATERIAL	651.40				
													1		LS	EROSION PREVENTION AND SEDIMENT CONTROL PLAN	652.10				
													160		HR	MONITORING EROSION PREVENTION AND SEDIMENT CONTROL PLAN	652.20				
													1		LU	MAINTENANCE OF EROSION PREVENTION AND SEDIEMTN CONTROL PLAN (N.A.B.I.)	652.30				
													620		SY	EROSION MATTING	654.10				
		8											8		EACH	REMOVING SIGNS	675.50				
		1											1		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40				
		2											2		EACH	TEMPORARY DETECTOR	678.42				

PROJECT NAME: HUNTINGTON
 PROJECT NUMBER: BRO 1445 (29)
 FILE NAME: Quantity Sheet PLOT DATE: 4/20/2004
 PROJECT LEADER: M. CHENETTE DRAWN BY: J. OAKMAN
 DESIGNED BY: D. ALTERI CHECKED BY: D. ALTERI
 QUANTITY SHEET #2 SHEET 6 OF 63

