STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAST Metric

APPROXIMATE SUMMARY OF QUANTITIES

		EMPLOYEE TRAINING	GOV'T PARTICIPATING BRIDGE	GOV'T PARTICIPATING ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				1,425	1,425	M	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	6.3
				510	510	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
				2,500	2,500	HR	FLAGGERS	630.15	EST
				1	1	LS	FIELD OFFICE - ENGINEERS	631.10	--
				1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	--
				1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	--
				1	1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	EST
		520			520	HR	EMPLOYEE TRAINEESHIP	634.10	--
				1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST
				1	1	LS	TRAFFIC CONTROL	641.10	EST
				16,800	16,800	M	100 MM WHITE LINE	646.20	--
				16,800	16,800	M	100 MM YELLOW LINE	646.21	--
				20	20	M	600 MM STOP BAR	646.26	--
				33	33	EA	LETTER OR SYMBOL	646.30	--
				33,600	33,600	M	TEMPORARY 100 MM WHITE LINE (PAINT)	646.60	EST
				33,600	33,600	M	TEMPORARY 100 MM YELLOW LINE (PAINT)	646.61	EST
				40	40	M	TEMPORARY 600 MM STOP BAR (PAINT)	646.66	EST
				48	48	EA	TEMPORARY LETTER OR SYMBOL (PAINT)	646.70	--
				1,000	1,000	EA	LINE STRIPING TARGETS	646.76	EST
				525	525	M2	GEOTEXTILE UNDER STONE FILL	649.31	EST
				500	500	M2	GEOTEXTILE FOR SILT FENCE	649.51	EST
				70	70	KG	SEED	651.15	EST
				50	50	KG	SEED - WINTER RYE	651.17	EST
				560	560	KG	FERTILIZER	651.18	EST
				5	5	T	AGRICULTURAL LIMESTONE	651.20	EST
				5	5	T	HAY MULCH	651.25	EST
				200	200	EA	HAY BALES FOR EROSION CONTROL	651.26	EST
				100	100	M3	TOPSOIL	651.35	EST
				2000	2000	M2	EROSION MATTING	654.10	EST
				9.0	9.0	M2	TRAFFIC SIGNS, TYPE A	675.20	0.93
							BEGIN OPTION ITEMS		
				70	70	M	FLANGED CHANNEL SIGN POST	675.301	1.0
				~~70~~	~~70~~	~~M~~	~~SQUARE TUBE STEEL SIGN POSTS AND ANCHOR~~	~~675.341~~	~~1.0~~
							END OPTION ITEMS		
				11	11	EA	REMOVING SIGNS	675.50	--
				1	1	EA	ERECTING SALVAGED SIGNS	675.60	--
				40	40	EA	DELINEATORS WITH STEEL POSTS	676.10	--
				1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	--

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	meters	kilometers	REMARKS

TOTALS

QUANTITY SHEET #2

PROJECT NAME **LUNENBURG** pave/01c150/pc150.dgn
PROJECT NUMBER **STP 2301(7)S** pc150qs2.1

DATE PLOTTED 10-AUG-2007 14:38

SHEET **5** OF **20** SHEETS