

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
			ROADWAY	TRAINING	EROSION CONTROL	UTILITES	UTILITES - (NON-PARTICIPATIN)	BRIDGE	FULL E & C ITEMS		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
														BEGIN OPTION AA						
			128								128		LF	18" CSP .079 (2-2/3 X 1/2)	601.0016					
			128								128		LF	18" CAAP .075 (2-2/3 X 1/2)	601.0216					
			128								128		LF	18" PCCSP .079 (2-2/3 X 1/2)	601.0416					
			128								128		LF	18" CPEP	601.0915					
														END OPTION AA						
			3								3		EACH	PRECAST REINFORCED CONCRETE CURB DI WITH CAST IRON GRATE	604.30					
			62								62		LF	6 INCH UNDERDRAIN PIPE	605.10					
			10								10		LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20					
			1								1		EACH	UNDERDRAIN FLUSHNG BASIN	605.95					
					10						10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25					
					2						2		MGAL	DUST CONTROL WITH WATER	609.10					
			75								75		CY	STONE FILL, TYPE II	613.11					
								470			470		CY	STONE FILL, TYPE IV	613.13					
			60								60		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28					
			12								12		TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47					
			40								40		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10					
			6								6		SF	DETECTABLE WARNING SURFACE	618.30					
			292.5								292.5		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21					
			4								4		EACH	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53					
			5								5		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60					
			75								75		LF	REMOVE AND RESET GUARDRAIL	621.75					
			420								420		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80					
						141					141		LF	DUCTILE IRON PIPE, CEMENT-LINED (8")	629.24					
						1					1		EACH	GATE VALVE WITH VALVE BOX (8")	629.27					
						1					1		EACH	RELOCATE HYDRANT	629.29					
							260				260		LF	PLASTIC WATER PIPE, RIGID (2")	629.33					
						1					1		EACH	TAPPING SLEEVE AND VALVE WITH VALVE BOX	629.35					
						1					1		LS	TRANSFER TO NEW SYSTEM, WATER SYSTEM	629.42					
			100								100		HR	FLAGGERS	630.15					
									1		1		LS	FIELD OFFICE, ENGINEERS	631.10					
									1		1		LS	TESTING EQUIPMENT, CONCRETE	631.16					
									1		1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17					
									1		1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25					
				520							520		HR	EMPLOYEE TRAINEESHIP	634.10					
			1								1		LS	MOBILIZATION/DEMobilIZATION	635.11					
			1								1		LS	TRAFFIC CONTROL	641.10					
			800								800		LF	4 INCH WHITE LINE	646.20					
			800								800		LF	4 INCH YELLOW LINE	646.21					
			75								75		SY	GEOTEXTILE UNDER STONE FILL	649.31					

PROJECT NAME: **BARTON**
PROJECT NUMBER: **BRO 1449(29)**
FILE NAME: /str5/01j168/sj168qs.xls PLOT DATE: 04/02/2007
PROJECT MANAGER: W. SYMONDS DRAWN BY: R. PELLETT
DESIGNED BY: J. LACROIX CHECKED BY: T. SUMNER
QUANTITY SHEET #2 SHEET 5 OF 84