

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
						240				240		CY	COMMON EXCAVATION	203.15				
						240				240		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
								130		130		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
								200		200		CY	COFFERDAM EXCAVATION, EARTH	208.30				
								50		50		CY	COFFERDAM EXCAVATION, ROCK	208.35				
								1		1		LS	COFFERDAM (ABUTMENT 1)	208.40				
								1		1		LS	COFFERDAM (ABUTMENT 2)	208.40				
						270				270		CY	SUBBASE OF GRAVEL	301.15				
						90				90		CY	AGGREGATE SURFACE COURSE	401.10				
								74		74		CY	CONCRETE, HIGH PERFORMANCE CLASS A (FPO)	501.33				
								66		66		CY	CONCRETE, HIGH PERFORMANCE CLASS B (FPO)	501.34				
								1		1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10				
								256		256		LF	STEEL PILING FOR INTEGRAL ABUTMENTS, HP 12 X 84	505.265				
								2		2		EACH	DYNAMIC PILE LOADING TEST	505.45				
								8190		8190		LB	REINFORCING STEEL (FPO)	507.15				
								12690		12690		LB	EPOXY COATED REINFORCING STEEL (FPO)	507.17				
								10		10		GAL	WATER REPELLENT, SILANE	514.10				
								88		88		LF	BRIDGE RAILING, GALVANIZED HDSB/FASCH MOUNTED/STEEL TUBING (FPO)	525.44				
								1		1		EACH	REMOVAL OF STRUCTURE (294 SF - EST.)	526.15				
						1				1		MSAL	DUST CONTROL WITH WATER	609.10				
								220		220		CY	STONE FILL, TYPE IV	613.13				
						180				180		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED (FPO)	621.21				
						4				4		EACH	ANCHOR FOR STEEL BEAM RAIL (FPO)	621.60				
						56				56		LF	REMOVAL AND DISPOSAL OF GUARDRAIL (FPO)	621.80				
						100				100		HR	FLAGGERS	630.15				
								1		1		LS	FIELD OFFICE, ENGINEERS	631.10				
								1		1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
								3000		3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
						1				1		LS	TRAFFIC CONTROL	641.10				
							115			115		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							150			150		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
							47			47		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							5			5		LB	SEED	651.15				
							50			50		LB	FERTILIZER	651.18				
							0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20				
							0.5			0.5		TON	HAY MULCH	651.25				
							20			20		CY	TOPSOIL	651.35				
							50			50		SY	GRUBBING MATERIAL	651.40				

PROJECT NAME: MENDON
PROJECT NUMBER: BRO 1443(43)

FILE NAME: 8/9/27298.xls
PROJECT LEADER: K. HIGGINS
DESIGNED BY: G. LAROCHE
QUANTITY SHEET #1

PLOT DATE: 08-SEP-2010
DRAWN BY: R. PELLETT
CHECKED BY: G. LAROCHE
SHEET 4 OF 32