

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						10				10		HR	TRUCK RENTAL	608.37				
						10				10		HR	LOADER RENTAL, TYPE I	608.40				
						0.5				0.5		MGAL	DUST CONTROL WITH WATER	609.10				
						0.5				0.5		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
						10				10		CY	STONE FILL, TYPE III	613.12				
						150				150		LF	VERTICAL GRANITE CURB	616.21				
						2				2		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10				
						40				40		LF	REMOVAL OF EXISTING FENCE	620.55				
						141				141		LF	BOX BEAM GUARDRAIL (COATED BLACK)	621.30				
								4		4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM (COATED BLACK)	621.72				
						95				95		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						160				160		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1				1		LS	TRAFFIC CONTROL	641.10				
						3				3		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						100				100		LF	4 INCH YELLOW LINE	646.21				
						20				20		LF	24 INCH STOP BAR	646.26				
						4				4		EACH	LETTER OR SYMBOL	646.30				
						30		150		180		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							75			75		SY	GEOTEXTILE FOR SILT FENCE	649.51				
						25				25		LB	SEED	651.15				
						25				25		LB	SEED, WINTER RYE	651.17				
						150				150		LB	FERTILIZER	651.18				
						0.7				0.7		TON	AGRICULTURAL LIMESTONE	651.20				
						0.7				0.7		TON	HAY MULCH	651.25				
						170				170		CY	TOPSOIL	651.35				
							1			1		LS	EPSC PLAN	652.10				
						80				80		HR	MONITORING EPSC PLAN	652.20				
						1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
						800				800		SY	TEMPORARY EROSION MATTING	653.20				
						10				10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
						40				40		CY	VEHICLE TRACKING PAD	653.35				
							2			2		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
						700				700		LF	PROJECT DEMARCATION FENCE	653.55				
						54				54		SF	TRAFFIC SIGNS, TYPE A	675.20				
						140				140		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
						8				8		EACH	REMOVING SIGNS	675.50				

900.680 SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)  
 136 TON TYPE IIS  
 171 TON TYPE IVS  
 307 TON SUBTOTAL  
 8 TON ROUND  
 315 TON TOTAL

PROJECT NAME: CORINTH  
 PROJECT NUMBER: BRO 1447(29)  
 FILE NAME: ...drawing\z01j292\_frm.dgn PLOT DATE: 8/4/2014  
 PROJECT LEADER: G. BOGUE DRAWN BY: E. ALLING  
 DESIGNED BY: M. CHENETTE CHECKED BY: G. BOGUE  
**QUANTITY SHEET - QTY 2** SHEET 7 OF 57

