



44.27 T = NEXT BEAM
 3.15 T = CURTAIN WALL (MARK END)
 3.15 T = CURTAIN WALL (NON-MARK END)
 50.57 T = TOTAL BEAM WT.

MATERIAL LIST / CURTAIN WALL				
ITEM	MARK	DESCRIPTION	QTY./CURTAIN WALL	
			MARK END	NON-MARK END
1	CR-404L	#4 BENT BAR (LEVEL II, DUAL COATED)	2	2
2	CR-508L	#5 BENT BAR (LEVEL II, DUAL COATED)	8	8
3	CR-509L	#5 BENT BAR (LEVEL II, DUAL COATED)	9	9
4				
5		#5 x 9'-10" (LVL. II, DUAL COATED)	5	5
6		#5 x 8'-10" (LVL. II, DUAL COATED)	4	4
7				
8				
9				
10				

APPROVED: Approval of drawings and/or procedures indicates concurrence with the information presented and does not relieve the Contractor or Fabricator of compliance with all requirements and code.

APPROVED AS NOTED

REVISE AND RESUBMIT

NOT REVIEWED

Date: 3/27/2015

By: Michael J. Chenette

This review by Stantec Consulting Services Inc. is for the sole purpose of ascertaining conformance with the general design concept. This review shall not mean that Stantec Consulting Services Inc. approves the detail design inherent in the shop drawings, responsibility for which shall remain with the Contractor. Submitting same, and such review shall not relieve the Contractor of his responsibility for errors or omissions in the shop drawing or of his responsibility for meeting all requirements of the Contract Documents. The contractor is responsible for dimensions to be confirmed and correlated at the job-site, for information that pertains solely to the fabrication processes or to techniques of construction and installation and for coordination of the work of all subtrades.

03-13-15 REVISED PER EOR COMMENTS

APPROVAL STAMP:

J.P. CARRARA & SONS INC.
 Precast & Prestress Manufacturer
 2464 CASE STR., MIDDLEBURY, VERMONT 05753 Phone:(802)388-6361 Fax:(802)388-9010

AUSTIN CONSTRUCTION, INC.
 CONTRACTOR
 CONCORD, VERMONT

STATE OF VERMONT AGENCY OF TRANSPORTATION
 COUNTY OF ORANGE

TOWN OF CORINTH
 CHICKEN FARM ROAD T.H.16 CLASS 3 LOCAL ROAD
 BRIDGE NO.: 36 PROJECT NO.: BRO 1447 (29)

DATE: MAR. 13, 2015
 SCALE: NOTED
 CHKD: RM DFTM: PSS
 JOB NO: 23448-014
 DWG. NO: NB3.2

PRECAST CURTAIN WALL DETAILS