



NEXT BEAM & CURTAIN WALL MISCELLANEOUS MATERIALS				
ITEM	MARK	QTY.	DESCRIPTION	REMARKS
1		54	#4 x 8'-11" (LEVEL II, DUAL COATED)	
2				
3		606	#5 x 7'-8 1/2" (LEVEL II, DUAL COATED)	
4		24	#5 x 7'-9" (LEVEL II, DUAL COATED)	
5		24	#5 x 7'-10" (LEVEL II, DUAL COATED)	
6		24	#5 x 7'-11" (LEVEL II, DUAL COATED)	
7		12	#5 x 8'-0" (LEVEL II, DUAL COATED)	
8		12	#5 x 8'-1" (LEVEL II, DUAL COATED)	
9		12	#5 x 8'-2" (LEVEL II, DUAL COATED)	
10		12	#5 x 8'-3" (LEVEL II, DUAL COATED)	
11		12	#5 x 8'-4" (LEVEL II, DUAL COATED)	
12		12	#5 x 8'-5" (LEVEL II, DUAL COATED)	
13		12	#5 x 8'-6" (LEVEL II, DUAL COATED)	
14		24	#5 x 8'-8" (LEVEL II, DUAL COATED)	
15		12	#5 x 8'-9" (LEVEL II, DUAL COATED)	
16		26	#5 x 8'-10" (LEVEL II, DUAL COATED)	
17		20	#5 x 9'-10" (LEVEL II, DUAL COATED)	
18		8	#5 x 10'-9" (LEVEL II, DUAL COATED)	
19		33	#5 x 70'-8" (W/ (1) 2'-6" STAGGERED LAP) (40' + 33'-2") (LVL. II, DUAL COATED)	
20		33	#5 x 61'-5" (W/ (1) 2'-6" STAGGERED LAP) (40' + 23'-11") (LVL. II, DUAL COATED)	
21		8	#4 x 61'-6" (W/ (1) 2'-6" STAGGERED LAP) (LVL. II, DUAL COATED)	TO BE SHIPPED LOOSE AT THE JOBSITE
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33	MK-CR1	30	MODIFIED UNIVERSAL 4APR DECK FORM HANGER 45" (GALV.) (20" LG.)	
34		12	SET OF (4) 0.60" x 270 KSI STRAND LIFTING LOOPS	
35		12	2" I.D. PVC SLEEVE	
36				
37				
38				

PRESTRESSED NEXT BEAMS

APPROVED: Approval of drawings and/or procedures indicates concurrence with the information presented and does not relieve the Contractor or Fabricator of compliance with all specifications and code requirements

APPROVED AS NOTED

REVISE AND RESUBMIT

NOT REVIEWED

Date: 3/27/2015

By: Michael J. Chenette

This review by Stantec Consulting Services Inc. is for the sole purpose of ascertaining conformance with the general design concept. This review shall not mean that Stantec Consulting Services Inc. approves the detail design inherent in the shop drawings, responsibility for which shall remain with the Contractor. Submitting same, and such review shall not relieve the Contractor of his responsibility for errors or omissions in the shop drawing or of his responsibility for meeting all requirements of the Contract Documents. The contractor is responsible for dimensions to be confirmed and correlated at the job site, for information that pertains solely to the fabrication processes or to techniques of construction and installation and for coordination of the work of all subtrades.

Stantec

03-13-15 REVISED PER EOR COMMENTS

APPROVAL STAMP:

DATE:	MAR. 13, 2015
SCALE:	NOTED
CHKD: RM	DFTM: PSS
JOB NO:	23448-014
DWG. NO:	M1

J.P. CARRARA & SONS INC. Precast & Prestress Manufacturer
2464 OSE STR., MIDDLEBURY, VERMONT 05753 Phone:(802)388-6361 Fax:(802)388-9010

AUSTIN CONSTRUCTION, INC. CONTRACTOR
CONCORD, VERMONT

STATE OF VERMONT AGENCY OF TRANSPORTATION
COUNTY OF ORANGE

TOWN OF CORINTH
CHICKEN FARM ROAD T.H.16 CLASS 3 LOCAL ROAD
BRIDGE NO.: 36 PROJECT NO.: BRO 1447 (29)

MATERIALS LIST