

QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES											DETAILED SUMMARY OF QUANTITIES			DETAILED SUMMARY OF QUANTITIES			
		LAND-SCAPING	FULL E&C	EROSION CONTROL	HEADWALL	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND	QUANTITIES	UNIT	ITEMS	QUANTITIES	UNIT	ITEMS
						20	20	EA	CONCRETE CATCH BASIN W/ CAST IRON GRATE	604.10	-						
						4	4	EA	CAST IRON GRATE WITH FRAME, TYPE D	604.47	-						
						750	750	M	150 MM UNDERDRAIN	605.10	30						
						30	30	M	150 MM UNDERDRAIN CARRIER PIPE	605.20	15						
						25	25	EA	UNDERDRAIN FLUSHING BASINS	605.95	-						
						50	50	HR	ROADWAY PATROL MAINTENANCE	607.10	18						
						10	10	HR	BULLDOZER RENTAL, TYPE I	608.10	EST						
						10	10	HR	POWER GRADER RENTAL	608.15	EST						
						10	10	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST						
						10	10	HR	POWER BROOM RENTAL	608.30	EST						
						10	10	HR	TRUCK RENTAL	608.37	EST						
						10	10	HR	LOADER RENTAL, TYPE I	608.40	EST						
						930	930	M ³	DUST CONTROL WITH WATER	609.10	EST						
						1.6	1.6	T	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	EST						
				10			10	M ³	STONE FILL TYPE I	613.10	EST						
					21	3.0	24	M ³	STONE FILL TYPE II	613.11	7.0						
						815	815	M	VERTICAL GRANITE CURB	616.21	4.2						
						8	8	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-						
						630	630	M ²	PORTLAND CEMENT CONCRETE SIDEWALK, 125 MM	618.10	4						
						2	2	EA	REMOVING AND RESETTING PROPERTY MARKERS	619.20	EST						
						25	25	M	REMOVING AND RESETTING FENCE	620.50	1						
						38	38	M	STEEL BEAM GUARD RAIL	621.20	6.1						
						4	4	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-						
						25	25	M	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	6.0						
						25	25	M	SEAMLESS COPPER WATER TUBE(3/4')	629.23	EST						
						5	5	EA	EXTENSION SERVICE BOX AND CURB STOP	629.25	EST						
						25	25	M	PLASTIC WATER PIPE, RIGID(8" CL150 PVC WATERLINE)	629.33	EST						
						25	25	M	PIPE INSULATION	629.44	EST						
						130	130	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST						

PROJECT NAME: FRANKLIN
 PROJECT NUMBER: STP 030(18)
 FILE NAME: ...85c060/desigr/dc060pms.dgn PLOT DATE: 24-APR-2003
 PROJECT LEADER: DELLASANTA DRAWN BY: SQUAD B
 DESIGNED BY: SQUAD B CHECKED BY: SQUAD B
 IPAM FILE NAME: (2)dc060q02.1 SHEET 5 OF 60