STATE OF VERMONT
AGENCY OF TRANSPORTATION

# ITEM DETAIL SHEET

Metric

## GUARD RAIL

| BEGIN STATION km + m | END STATION km + m | POSITION LEFT m | POSITION RIGHT m | END TREATMENT BEGIN EA | END TREATMENT END EA |
|---|---|---|---|---|---|
| 15+279 | 15+294 | | 20.27 | | |
| ~~15+277~~ LT | ~~15+295~~ LT | | ~~19~~ | STA. G-1dm | |
| 15+272 | 15+291 | | 16.46 | | |
| ~~15+275~~ RT | ~~15+290~~ RT | | ~~19~~ | STA. G-1dm | |
| | | | 36.73 | | |
| | TOTALS | | ~~38~~ | | |
| ANCHORS FOR STEEL BEAM RAIL | | | | 621.60 | 4 EA. |

## UNDERDRAIN

| BEGIN STATION km + m | END STATION km + m | TYPE | POSITION | DIA. mm | LENGTH m | TRENCH EARTH m³ | TRENCH ROCK m³ | GRAN BKFILL m³ | FB EA | MKR PST EA |
|---|---|---|---|---|---|---|---|---|---|---|
| FRANKLIN | | | | | | | | | | |
| 15+032 | 15+046.5 | U | RT | 150 | 16 | 5.2 | | | | |
| 15+048 | 15+098 | U | RT | 150 | 51 | 23.6 | | | 1 | |
| 15+098 | 15+124 | U | LT | 150 | 24 | 9.6 | | | 1 | |
| 15+099.5 | 15+156.5 | U | RT | 150 | 57 | 38.6 | | | 1 | |
| 15+125.5 | 15+173.5 | U | LT | 150 | 49 | 33.7 | | | 1 | |
| 15+158 | 15+189.5 | U | RT | 150 | 15 | 11.1 | | | 1 | |
| 15+175 | 15+191 | U | LT | 150 | 17 | 8.7 | | | 1 | |
| 15+190 | 15+214 | U | RT | 150 | 23 | 0.0 | | | 1 | |
| 15+215 | 15+258.5 | U | RT | 150 | 44 | 0.0 | | | 1 | |
| 15+259.5 | 15+276 | U | RT | 150 | 16.5 | 8.3 | | | 1 | |
| 15+293 | 15+310 | U | RT | 150 | 16 | 10.0 | | | 1 | |
| 15+311 | 15+317.5 | U | RT | 150 | 8 | 5.0 | | | 1 | |
| 15+319 | 15+343.5 | U | RT | 150 | 24 | 9.4 | | | 1 | |
| 15+345 | 15+361.5 | U | RT | 150 | 17 | 7.9 | | | 1 | |
| 15+363 | 15+381.5 | U | RT | 150 | 19 | 7.9 | | | 1 | |
| 15+363 | 15+413.5 | U | LT | 150 | 51.0 | 14.0 | | | 1 | |
| 15+383 | 15+424 | U | RT | 150 | 41.5 | 21.8 | | | 1 | |
| 15+415 | 15+438.5 | U | LT | 150 | 24.0 | 8.3 | | | 1 | |
| 15+425 | 15+438.5 | U | RT | 150 | 13.5 | 3.3 | | | 1 | |
| TH # 16 | | | | | | | | | | |
| 26+060 | 26+039 | U | RT | 150 | 22.0 | 10.5 | | | 1 | 1 |
| 26+037.5 | 26+013 | U | RT | 150 | 23.0 | 12.7 | | | 1 | |
| 26+013 | 26+013 | U | RT/LT | 150 | 5.0 | 4.0 | | | 1 | |
| 26+060 | 26+036.5 | U | LT | 150 | 23.0 | 11.9 | | | 1 | 1 |
| 26+035 | 26+013 | U | LT | 150 | 23.0 | 11.1 | | | 1 | |
| M/L 15+192.5 | TH 26+013 | U | LT | 150 | 17.0 | 9.0 | | | 1 | |
| EST. UNDERDRAIN | | U | | 150 | 80 | 751 | | | 1 | 1 |
| EST. CARRIER | | C | | 150 | 15.0 | 29.0 | | | | |
| TOTAL | | U | | 150 | 720 | 1036 | | | 25 | 3 |
| TOTAL | | C | | 150 | 15.0 | 29.0 | | | | |
| TOTAL TRENCH EARTH | | | | | | 1066 | | | | |
| TOTAL F/B AND MP | | | | | | | | | 25 | 3 |

| BEGIN STATION km + m | END STATION km + m | POSITION LEFT m | POSITION RIGHT m | REMARKS |
|---|---|---|---|---|

| BEGIN STATION km + m | END STATION km + m | POSITION LEFT m | POSITION RIGHT m | REMARKS |
|---|---|---|---|---|

| BEGIN STATION km + m | END STATION km + m | POSITION LEFT m | POSITION RIGHT m | REMARKS |
|---|---|---|---|---|

PROJECT NAME: FRANKLIN
PROJECT NUMBER: STP 0301(18)

FILE NAME: ...85c060/design/dc060pms.dgn PLOT DATE: 27-MAR-2003
PROJECT LEADER: DELLASANTA DRAWN BY: SQUAD B
DESIGNED BY: SQUAD B CHECKED BY: SQUAD B
IPAM FILE NAME: (2)dc0601dl.i SHEET 10 OF 60