

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES													TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
			SUPER STRUCT.	ABUT. #1	ABUT. #2	ROADWAY	E & C ITEMS	EROSION CONTROL		BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS		
						1						1		LS	CLEARING AND GRUBBING (Including Individual Trees and Stumps)	201.10					
						330						330		CY	COMMON EXCAVATION	203.15					
		5		25								30		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27					
								10				10		CY	TRENCH EXCAVATION OF EARTH	204.20					
						310		10				320		CY	SUBBASE OF GRAVEL	301.15					
						2						2		CWT	EMULSIFIED ASPHALT	404.65					
						135						135		TON	MEDIUM DUTY BIT. CONC. PAVEMENT (PG 58-28)	406.27					
		18		14								32		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34					
	1											1		LS	SHORING SUPERSTRUCTURE (MOD.)	502.10					
			300									300		LB	STRUCTURAL STEEL	506.60					
			16									16		LF	DRAIN TROUGH (MOD.)	506.80					
			1906		1812							3718		LB	REINFORCING STEEL	507.15					
			24		24							48		LF	DRILLING AND GROUTING DOWELS	507.16					
	1											1		LS	STRUCTURAL PAINTING, FIELD APPLIED (MOD.)	513.30					
	1											1		LS	CONTAINMENT & ENVIRON. PROTECTION, FIELD (MOD.)	513.36					
		3		2								5		GAL	WATER REPELLENT (MOD. - SILANE)	514.10					
	0.60											0.60		MFBM	STRUCTURAL LUMBER AND TIMBER - UNTREATED	522.20					
	5.10											5.10		MFBM	STRUCTURAL LUMBER AND TIMBER - TREATED (FLOOR BEAMS)	522.25					
	3.25											3.25		MFBM	STRUCTURAL LUMBER AND TIMBER - TREATED (DECKING)	522.25					
	6.00											6.00		MFBM	NON - STRUCTURAL LUMBER-UNTREATED	522.30					
	1											1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20					
	4											4		EACH	BEARING DEVICE ASSEMBLY (MOD.)	531.10					
					16							16		SY	REPOINTING MASONRY (MOD.)	602.30					
								10				10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25					
								1				1		TON	DUST & ICE CONTROL WITH CALCIUM CHLORIDE	609.15					
								10				10		CY	STONE FILL, TYPE I	613.10					
		13		35								48		CY	STONE FILL, TYPE III	613.12					
						425						425		LF	SNOW FENCE (MOD-PDF)	620.70					
						168						168		LF	HVY DUTY STEEL BEAM GUARD RAIL. (w/Wood Posts)	621.21					
						4						4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.80					
						56						56		LF	REMOVL AND DISP OF GUARD RAIL	621.80					
							1					1		LS	FIELD OFFICE-ENGINEERS	631.10					
							1					1		LS	TESTING EQUIPMENT - CONCRETE	631.16					
							1					1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17					
							1					1		LU	FIELD OFFICE - TELEPHONE (NABI)	631.25					
						1						1		LS	MOBILIZATION/DEMOLITION	635.11					
						1						1		LS	TRAFFIC CONTROL	641.10					
								61				61		SY	GEOTEXTILE UNDER STONE FILL	649.31					
								151				151		SY	GEOTEXTILE FOR SILT FENCE	649.51					
								105				105		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61					

PROJECT NAME: **Tunbridge**  
PROJECT NUMBER: **BHO 1444 (42)**  
FILE NAME: 03j032/str/s03j032excel.dgn PLOT DATE: 08/30/2005  
PROJECT MANAGER: C.P. Williams DRAWN BY: R.S. Young  
DESIGNED BY: R.S. Young CHECKED BY: M.LONGSTREET  
QUANTITY SHEET #1 SHEET 3 OF 40