

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES													TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
FULL E&C ITEMS	ROADWAY	ABUT. 1	ABUT. 2	PIER	DECK	TRUSS	EROSION CONTROL	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FNAL	UNIT	ITEMS	ITEM NUMBER	QUAN TITIES	UNIT	ITEMS				
	1									1		LS	CLEARING AND GRUBBING (INCL. INDV. TREES AND STUMPS)	201.10							
	130									130		CY	COMMON EXCAVATION	203.15							
	225									225		CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28							
							10			10		CY	TRENCH EXCAVATION OF EARTH	204.20							
		150	30					180		180		CY	STRUCTURE EXCAVATION	204.25							
		120						120		120		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30							
	190						10			200		CY	SUBBASE OF GRAVEL	301.15							
	3									3		CWT	EMULSIFIED ASPHALT	404.65							
	325									325		TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.25							
		16						16		16		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34							
						1		1		1		LS	SHORING SUPERSTRUCTURE (COVERED BRIDGE)	502.10							
					4540			4540		4540		LB	STRUCTURAL STEEL	506.60							
		1100						1100		1100		LB	EPOXY COATED REINFORCING STEEL	507.17							
					1			1		1		LS	STRUCTURAL PAINTING, SHOP APPLIED (2 TONS)	513.25							
						1		1		1		LS	STRUCTURAL PAINTING, FIELD APPLIED (MOD. - INSECTICIDE AND FIRE RETARDANT)	513.30							
					1			1		1		LS	STRUCTURAL PAINTING, FIELD APPLIED (35 TONS)	513.30							
					1			1		1		LS	CONTAINMENT & ENVIRONMENTAL PROTECTION, FIELD	513.36							
						1		1		1		LS	CONTAINMENT & ENVIRONMENTAL PROTECTION, FIELD (MOD. - INSECTICIDE AND FIRE RETARDANT)	513.36							
					1			1		1		LS	SURFACE PREPARATION, SHOP (2 TONS)	513.40							
					1			1		1		LS	SURFACE PREPARATION, FIELD (35 TONS)	513.41							
		1	1	4				6		6		GAL	WATER REPELLENT (MOD. - SILANE)	514.10							
					4.8			4.8		4.8		MFBM	STRUCTURAL LUMBER AND TIMBER - UNTREATED	522.20							
						7.1		7.1		7.1		MFBM	STRUCTURAL LUMBER AND TIMBER - TREATED	522.25							
						6		6		6		MFBM	NON - STRUCTURAL LUMBER-UNTREATED	522.30							
					1			1		1		LS	STRUCTURAL GLUED LAMNATED TIMBER (DECK)	522.40							
					7			7		7		GAL	JOINT SEALER, COLD POURED	524.12							
	1							1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20							
	4							4		4		EACH	BEARING DEVICE ASSEMBLY (FABRIC)	531.10							
	2							2		2		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE CLASS I	580.13							
	2							2		2		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE CLASS II	580.14							
	2							2		2		CY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE CLASS III	580.15							
	32							32		32		SY	REPOINTING MASONRY (MOD.)	602.30							
							1			1		HR	BULLDOZER RENTAL, TYPE I	608.10							
	2									2		HR	POWER GRADER RENTAL	608.15							
							1			1		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25							
							10			10		CY	STONE FILL, TYPE I (MOD. - CONSTRUCTION ENTRANCE)	613.10							
							2			2		CY	STONE FILL, TYPE I	613.10							
							1			1		TON	BITUMINOUS CONCRETE SIDEWALK (MOD.)	618.15							
							170			170		LF	SNOW FENCE (MOD. - PDF)	620.70							

PROJECT NAME: **THETFORD**  
 PROJECT NUMBER: **BHO 1444 (43)**  
 FILE NAME: s03j036qty.dgn PLOT DATE: 2/1/2006  
 PROJECT MANAGER: M. EVANS-MONGEON DRAWN BY: G. ROKES  
 DESIGNED BY: G. ROKES CHECKED BY: S. SCRIBNER  
 QUANTITY SHEET #1 SHEET 5 OF 60