



Bonding Procedure

The bonding process for laminating PTFE to the fabric pad is as follows:

The fabric pad surface to be bonded is prepared for lamination. A two-part structural grade epoxy is then applied per the manufacture's instructions. The PTFE is cut slightly oversize to account for the possible drift. The PTFE is then applied to the fabric pad and put into a vacuum press at the appropriate pressure for the necessary time period.

Once the fabric pad PTFE is removed from the press, the PTFE is trimmed to plan size and the pads are submitted for quality control review.

VTTRANS
RECEIVED
CHKD BY: JCC
APR 18 2007
RESUBMIT: _____ APPROVED: _____
BY: _____ DATE: 4-22-07

The D.S. Brown Company
300 E. Cherry Street
North Baltimore, Ohio 45872
419.257.3561
Fax: 419.257.2200
e-mail: dsb@dbsbrown.com
www.dsbrown.com

Lewis Engineering Company
4201 Norx Drive
Croska, Minnesota 55316
952.982.5000
Fax: 952.448.7000

International Division
27 Pioneer Road
Singapore 62608
65.862.2555
Fax: +65.862.8255
e-mail:
dsbrown@mbca2.singtel.com.sg

Equal Opportunity Employer

062 BB