



- CONSTRUCTION NOTES**
- CONSTRUCT SIDEWALK**
STA 10+575.0 - STA 10+603.0, LT
STA 10+613.3 - STA 10+660.0, LT
- CONSTRUCT SIDEWALK RAMP, TYPE I**
(SEE STD. C-3M)
STA 10+599.7 - STA 10+603.0, LT
STA 10+613.3 - STA 10+616.3, LT
- CONSTRUCT CONCRETE CURB**
STA 10+575 - STA 10+629.5, RT
STA 10+575 - STA 10+602.1, LT
STA 10+613.9 - STA 10+660, LT
- DURABLE 100 mm WHITE LINE**
STA 10+575 - STA 10+660, LT & RT
STA 10+648 - STA 10+660, RT TURNING LANE
- DURABLE 100 mm YELLOW LINE (DOUBLE CENTER LINE)**
STA 10+575 - STA 10+627.5
- DURABLE 100 mm YELLOW LINE (SINGLE CENTER LINE)**
STA 10+627.5 - STA 10+660, LT & RT
STA 10+627.5 - STA 10+648.5, LT & RT
- DURABLE 200 mm DIAGONAL YELLOW LINE**
STA 10+627.5 - STA 10+648
- DURABLE SYMBOL**
STA 10+653, RT ARROW-LEFT TURN
STA 10+653, RT ARROW-RIGHT TURN
- CONSTRUCT DRIVE**
STA 10+608, LT
50 BCP TYPE III, 6000 WIDE
- STA 10+639, RT
COLD PLANE, 2000 APRON
50 BCP TYPE III, 2000 APRON
- TRAVEL LANE TAPER**
STA 10+625.4, LT (3300) TO
STA 10+660, LT (5660)
- STA 10+598, RT (3300) TO
STA 10+648.5, RT (6300)
- PAVED SHOULDER TAPER**
STA 10+598, LT (1800) TO
STA 10+617.2, LT (2800) TO
STA 10+625.4, LT (2910) TO
STA 10+638.8, LT (3110) TO
STA 10+660, LT (300)
- STA 10+598, RT (1800) TO
STA 10+630, RT (300)
- COLD PLANING**
STA 10+645 - STA 10+660

FOR R.O.W. USE ONLY

DATUM
VERTICAL NAVD 88
HORIZONTAL NAD 83 (92)

STATE OF VERMONT AGENCY OF TRANSPORTATION			
Town Of COLCHESTER-SOUTH BURLINGTON	Bridge No. 6		
Highway No. TH 4/3	Log Sta.		
	Surv. Sta.		
TH 4/3 OVER WINOOSKI RIVER & N.E.C.R.			
PLAN (5 OF 5)			
Designed By A. J. CRAWFORD	Date 6/03	Drawn By C. S. MERCER	Date 6/03
Checked By J. A. MERCER	Date 6/03	Bridge Design Supervisor S. M. GUNN	Date 6/03
PROJECT COLCHESTER-SOUTH BURLINGTON		PROJECT NO. BRM 5600 (6) S C/2	
I.G.C. Info.		R.O.W. SHEET 21 OF 21	
		SHEET 14 OF 124	