

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES														TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES				
FULL C.E. ITEMS	ROADWAY	EROSION CONTROL	CHANNEL	ABUTMENT NO. 1	ABUTMENT NO. 2	WINGWALL NO. 1	WINGWALL NO. 2	WINGWALL NO. 3	WINGWALL NO. 4	SUPER-STRUCTURE	ALTERNATE A	ALTERNATE B	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS		
	1														1		LS	TRAFFIC CONTROL	641.10					
			79				21						100	5	100		SY	GEOTEXTILE UNDER STONE FILL	649.31					
		120												2	120		SY	GEOTEXTILE FOR SILT FENCE	649.51					
		100												7	100		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61					
		10												8	10		LB	SEED	651.15					
		20												7	20		LB	FERTILIZER	651.18					
		1.00												0.9	1		TON	AGRICULTURAL LIMESTONE	651.20					
		1.00												0.9	1		TON	HAY MULCH	651.25					
		10												3	10		CY	TOPSOIL	651.35					
		20												6	20		SY	GRUBBING MATERIAL	651.40					
		1													1		LS	EPSC PLAN	652.10					
		80													80		HR	MONITORING EPSC PLAN	652.20					
		1													1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30					
		130												3	130		SY	TEMPORARY EROSION MATTING	653.20					
		10													10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25					
	360														360		LF	PROJECT DEMARCATION FENCE	653.55					
	50.25														50.25		SF	TRAFFIC SIGNS, TYPE A	675.20					
	97.0													0.5	97		LF	FLANGED CHANNEL SIGN POST	675.301					
									18				18	3	18		CY	SPECIAL PROVISION (REBUILT STONE MASONRY)	900.608					
										10			10		10		EACH	SPECIAL PROVISION (BEARING DEVICE ASSEMBLY, COVERED BRIDGE)	900.620					
										13			13		13		EA	SPECIAL PROVISION (WOOD EPOXY REPAIRS)	900.620					
				1.7	2.4	1.6		0.5	0.8				7	0.5	7		GAL	SPECIAL PROVISION (CONCRETE STAINING AND SEALING)	900.625					
	284.75														284.75		LF	SPECIAL PROVISION (HD STEEL BEAM GUARDRAIL, WEATHERING) (WOOD POSTS)	900.640					
										1			1		1		LS	SPECIAL PROVISION (TIMBER PAINTING, ENVIRONMENTAL PROTECTION)	900.645					
										1			1		1		LS	SPECIAL PROVISION (TIMBER PAINTING, FIRE RETARDANT)	900.645					
										1			1		1		LS	SPECIAL PROVISION (TIMBER PAINTING, INSECTICIDE/FUNGICIDE)	900.645					
										1450			1450		1450		SF	SPECIAL PROVISION (METAL ROOFING)	900.670					
				12			10						22		22		SY	SPECIAL PROVISION (REPAIRING STONE MASONRY)	900.675					
																		BEGIN ALTERNATE ITEMS						
																		ALTERNATE A (IN-PLACE REHABILITATION)						
											1		1		1		LS	SHORING SUPERSTRUCTURE	502.10					
											1		1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20					
											1		1		1		LS	SPECIAL PROVISION (REHABILITATING COVERED BRIDGE SUPERSTRUCTURE)	900.645					
																		ALTERNATE B (RELOCATED REHABILITATION)						
												1	1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20					
												1	1		1		LS	SPECIAL PROVISION (HANDLING, TRANSPORT, AND RE-ERECTION OF COVERED BRIDGE SUPERSTRUCTURE)	900.645					
												1	1		1		LS	SPECIAL PROVISION (REHABILITATING COVERED BRIDGE SUPERSTRUCTURE)	900.645					
																		END ALTERNATE ITEMS						

PROJECT NAME: **FAIRFIELD**  
 PROJECT NUMBER: **BHO 1448(32)**  
 FILE NAME: Z04J144quant.xls PLOT DATE: 5/13/2008  
 PROJECT MANAGER: J.H.WEAVER DRAWN BY: J.BICJA  
 DESIGNED BY: J.BICJA CHECKED BY: S.T.JAMES  
 QUANTITY SHEET (2 OF 2) SHEET 6 OF 36