

QUANTITY SHEET (3 OF 3)

SUMMARY OF ESTIMATED QUANTITIES													TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	LAND-SCAPING	CHANNEL	ABUT #1	ABUT #2	SUPER-STRUCTURE	EROSION CONTROL	E & C ITEMS	UTILITY	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS			
						0.5					0.5		TON	HAYMULCH	651.25						
						10					10		CY	TOPSOIL	651.35						
						110					110		SY	GRUBBING MATERIAL	651.40						
						1					1		LS	EPSC PLAN	652.10						
						60					60		HR	MONITORING EPSC PLAN	652.20						
						1					1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30						
						110					110		SY	TEMPORARY EROSION MATTING	653.20						
						10					10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25						
370											370		LF	PROJECT DEMARCATION FENCE	653.55						
	1										1		EACH	DECIDUOUS TREES (SILVER MAPLE) (ACER SACCHARNUM) (4 - 6 FT)	656.30						
	1										1		EACH	DECIDUOUS TREES (BLACK WILLOW) (SALIX NIGRA) (4 - 6 FT)	656.30						
12.5											12.5		SF	TRAFFIC SIGNS, TYPE A	675.20						
28											28		LF	FLANGED CHANNEL SIGN POST	675.301						
2											2		EACH	REMOVING SIGNS	675.50						
2											2		EACH	ERECTING SALVAGED SIGNS	675.60						
2											2		EACH	SETTING SALVAGED POSTS	675.61						
			5	5	1					11	11		GAL	SPECIAL PROVISION (CONCRETE STAINING AND SEALING)	900.625						
129											129		LF	SPECIAL PROVISION (HDSB GUARDRAIL, WEATHERING W/8 FT POSTS (WOOD POSTS))	900.640						
						1				1	1		LS	SPECIAL PROVISION (INCORPORATING SALVAGED BRIDGE COMPONENTS)	900.645						
						1				1	1		LS	SPECIAL PROVISION (TIMBER PAINTING, ENVIRONMENTAL PROTECTION)	900.645						
						1				1	1		LS	SPECIAL PROVISION (TIMBER PAINTING, FIRE RETARDANT)	900.645						
						1				1	1		LS	SPECIAL PROVISION (TIMBER PAINTING, INSECTICIDE/FUNGICIDE)	900.645						
						1110				1110	1110		SF	SPECIAL PROVISION (METAL ROOFING)	900.670						

PROJECT NAME: **RANDOLPH**
 PROJECT NUMBER: **BHO 1444 (44)**
 FILE NAME: z04j146qnty.xls
 PROJECT MANAGER: S. HODGDON (VHB)
 DESIGNED BY: S. HODGDON
 QUANTITY SHEET (3 OF 3)

PLOT DATE: 7/2/2007
 DRAWN BY: K. WENTWORTH
 CHECKED BY: K. ZIENKIEWICZ
 SHEET 7 OF 39