

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES											TOTALS			DESCRIPTIONS		DETAILED SUMMARY OF QUANTITIES									
											ROADWAY	EROSION CONTROL	BRIDGE	ALTERNATE A	ALTERNATE B	FULL C/E ITEMS	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
												1						1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201 10			
											190							190		CY	COMMON EXCAVATION	203 15			
													168					168		CY	STRUCTURE EXCAVATION	204 25			
													95					95		CY	GRANULAR BACKFILL FOR STRUCTURES	204 30			
											145							145		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301 25			
											50							50		CY	AGGREGATE SURFACE COURSE	401 10			
													17					17		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501 34			
													310					310		LB	STRUCTURAL STEEL	506 60			
													942					942		LB	REINFORCING STEEL	507 15			
													6					6		LF	DRILLING AND GROUTING DOWELS	507 16			
													4					4		GAL	WATER REPELLENT, SILANE	514 10			
													47					47		MFBM	STRUCTURAL LUMBER AND TIMBER - UNTREATED	522 20			
													103					103		MFBM	STRUCTURAL LUMBER AND TIMBER - TREATED	522 25			
													2					2		MFBM	NON - STRUCTURAL LUMBER-UNTREATED	522 30			
													05					05		CY	MORTAR, TYPE IV	541 58			
													2					2		CY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE CLASS III	580 15			
													58					58		CY	DRY MASONRY	602 20			
													28					28		CY	STONE FILL, TYPE II	613 11			
											78							78		LF	STEEL BACKED TIMBER GUARD RAIL	621 18			
																	1	1		LS	FIELD OFFICE-ENGINEERS	631 10			
																	1	1		LS	TESTING EQUIPMENT - CONCRETE	631 16			
																	1	1		LU	FIELD OFFICE - TELEPHONE (N A B I)	631 25			
											1							1		LS	MOBILIZATION / DEMOBILIZATION	635 11			
											1							1		LS	TRAFFIC CONTROL	641 10			
													45					45		SY	GEOTEXTILE UNDER STONE FILL	649 31			
												55						55		SY	GEOTEXTILE FOR SILT FENCE	649 51			
												15						15		LB	SEED	651 15			
												15						15		LB	FERTILIZER	651 18			
												05						05		TON	AGRICULTURAL LIMESTONE	651 20			
												3						3		TON	HAYMULCH	651 25			
												10						10		CY	TOPSOIL	651 35			
												1						1		LS	EPSC PLAN	652 10			
												40						40		HR	MONITORING EPSC PLAN	652 20			
												1						1		LU	MAINTENANCE OF EPSC PLAN (N A B I)	652 30			
												25						25		SY	TEMPORARY EROSION MATTING	653 20			
												300						300		LF	PROJECT DEMARCATION FENCE	653 35			
											35							35		SF	TRAFFIC SIGNS, TYPE A	675 20			
											44							44		LF	FLANGED CHANNEL SIGN POST	675 301			
													7					7		CY	SPECIAL PROVISION (REBUILT STONE MASONRY)	900 608			
													77					77		LF	SPECIAL PROVISION (HD STEEL BEAM GUARDRAIL, WEATHERING / FASCIA MOUNTED) (WOOD POSTS)	900 640			

PROJECT NAME **MONTGOMERY**  
PROJECT NUMBER **BHO 1448(37)**  
FILE NAME s04j148n&q.dgn PLOT DATE 6/2/2008  
PROJECT MANAGER **J WEAVER** DRAWN BY **C WEEBER**  
DESIGNED BY **J WEAVER** CHECKED **J WEAVER**  
**QUANTITY SHEET #1** SHEET **3A** OF **35**