

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES													TOTALS				DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
STOWE BHO 1448(32)	WATERVILLE BHO 1448(33)	WATERVILLE BHO 1448(34)	BELVIDERE BHO 1448(35)	ENOSBURG BHO 1448(36)								BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS	
0.01	0.01	0.01	0.01	0.01								0.05		0.05		ACRE	THINNING AND TRIMMING	201.30				
-	-	6	-	-								6		6		CY	STRUCTURE EXCAVATION	204.25				
-	-	6	-	-								6		6		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
5	-	-	-	-								5		5		CY	AGGREGATE SURFACE COURSE	401.10				
0.25	0.25	0.25	0.25	-								1		1		LS	STRUCTURAL PAINTING, FIELD APPLIED (MOD.- FIRE RETARDANT)	513.30				
0.25	0.25	0.25	0.25	-								1		1		LS	CONTANMENT & ENVIRONMENTAL PROTECTION, FIELD (MOD.- FIRE RETARDANT)	513.36				
-	-	0.200	-	-								0.200		0.200		MFBM	STRUCTURAL LUMBER AND TIMBER - UNTREATED	522.20				
-	-	9	-	-								9		9		CY	DRY RUBBLE MASONRY (MOD.)	602.20				
67	74	55	30	69								295		295		SY	REPORTNG MASONRY (MOD.)	602.30				
3	-	-	5	-								8		8		CY	STONE FILL, TYPE II	613.11				
-	116.80	-	-	-								116.8		116.8		LF	PLANK RAIL (MOD.)	621.15				
151	-	71	-	-								222		222		LF	HEAVY DUTY STEEL BEAM GUARD RAIL (WEATHERING) (MOD.- 8FT. POSTS)	621.21				
-	-	-	111	-								111		111		LF	REMOVING AND RESET GUARD RAIL	621.75				
-	1	-	-	-								1		1		EA	REPLACE GUARD RAIL POST ASSEMBLY	621.76				
40	100	44	-	-								184		184		LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80				
5	5	5	5	5								25		25		HR	FLAGGERS	630.15				
0.20	0.20	0.20	0.20	0.20								1		1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
0.20	0.20	0.20	0.20	0.20								1		1		LS	TRAFFIC CONTROL	641.10				
14	-	36	10	-								60		60		SY	GEOTEXTILE FOR SILT FENCE	649.51				
-	-	5	-	-								5		5		LB	SEED	651.15				
-	-	5	-	-								5		5		LB	FERTILIZER	651.18				
5	-	5	3	-								13		13		EACH	HAY BALES FOR EROSION CONTROL	651.26				
-	-	2	-	-								2		2		CY	TOPSOIL	651.35				
0.20	0.20	0.20	0.20	0.20								1		1		LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30				
-	-	1400	-	-								1400		1400		SF	REMOVING EXISTING ROOF	665.15				
-	-	1400	-	-								1400		1400		SF	METAL ROOFING	665.18				
30.0	22.5	23.8	22.5	25.0								123.80		123.80		SF	TRAFFIC SIGNS, TYPE A	675.20				
44	44	33	44	22								187		187		LF	FLANGED CHANNEL SIGN POST	675.301				