

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS				DESCRIPTIONS		DETAILED SUMMARY OF QUANTITIES			
WOODSTOCK BHO 1444(45)	W. WINDSOR BHO 1444(46)	W. WINDSOR BHO 1444(47)								BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
0.01	0.01	0.01								0.03		0.03		ACRE	THINNING AND TRIMMING	201.30			
6	-	-								6		6		CY	STRUCTURE EXCAVATION	204.25			
6	-	-								6		6		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30			
0.50	0.25	0.25								1		1		LS	STRUCTURAL PAINTING, FIELD APPLIED (MOD.-FIRE RETARDANT)	513.30			
0.50	0.25	0.25								1		1		LS	CONTAINMENT & ENVIRONMENTAL PROTECTION, FIELD (MOD.- FIRE RETARDANT)	513.36			
-	-	0.10								0.10		0.10		MFBM	STRUCTURAL LUMBER AND TIMBER - UNTREATED	522.20			
1	-	-								1		1		LS	STRUCTURAL GLUED LAMINATED TIMBER (MOD.)	522.40			
9	-	-								9		9		CY	DRY RUBBLE MASONRY (MOD.)	602.20			
86	47	44								177		177		SY	REPOINTING MASONRY (MOD.)	602.30			
27	-	-								27		27		LF	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	621.21			
-	-	98								98		98		LF	HEAVY DUTY STEEL BEAM GUARD RAIL (WEATHERING)	621.21			
-	2	-								2		2		EACH	REPLACE GUARD RAIL POST ASSEMBLY (MOD.)	621.76			
25	-	-								25		25		LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80			
10	5	5								20		20		HR	FLAGGERS	630.15			
0.34	0.33	0.33								1		1		LS	MOBILIZATION/DEMOBILIZATION	635.11			
0.34	0.33	0.33								1		1		LS	TRAFFIC CONTROL	641.10			
38	-	-								38		38		SY	GEOTEXTILE FOR SILT FENCE	649.51			
5	-	-								5		5		LB	SEED	651.15			
5	-	-								5		5		LB	FERTILIZER	651.18			
5	-	-								5		5		EACH	HAY BALES FOR EROSION CONTROL	651.26			
2	-	-								2		2		CY	TOPSOIL	651.35			
0.50	0.25	0.25								1		1		LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30			
12.50	35	35								82.50		82.50		SF	TRAFFIC SIGNS, TYPE A	675.20			
22	44	44								110		110		LF	FLANGED CHANNEL SIGN POST	675.301			