

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES				
							ROADWAY	TRAINING	EROSION CONTROL	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							6500				6500		SY	COLD PLANING-BIT.PAVEMENT	210.10	519			
							150				150		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	3			
							1750				1750		SY	RECLAIMED STABILIZED BASE	310.20	268			
							40				40		TON	AGGREGATE SHOULDERS, RAP	402.13	10			
							20				20		CWT	EMULSIFIED ASPHALT	404.65	1			
							1250				1250		TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	408.25	6			BITUMINOUS CONCRETE PAVEMENT (PG 58-28)
							100				100		LF	CLEANING CULV. PIPE, IN-PLACE (0 TO 24 IN., INCL.)	601.995	8			
							40				40		HR	ROADWAY PATROL MAINTENANCE	607.10	-	837.3	TON	TYPE II - WEARING COURSE
							40				40		HR	BULLDOZER RENTAL, TYPE I	608.10	-	159.5	TON	TYPE IV - LEVELING COURSE
							40				40		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	-	247.0	TON	TYPE II - BASE COURSE
							10				10		HR	POWER BROOM RENTAL, TYPE I	608.30	-	6.2	TON	ROUNDING
							20				20		HR	TRUCK RENTAL	608.37	-	1250	TON	TOTAL
							40				40		HR	LOADER RENTAL, TYPE I	608.40	-			
							1				1		MGAL	DUST CONTROL WITH WATER	609.10	-			
							1				1		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	-			
							900				900		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	-			
							6				6		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
							687				687		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
							200				200		HR	UNIFORMED TRAFFIC OFFICERS	630.10	-			
							500				500		HR	FLAGGERS	630.15	-			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-			
							1				1		LS	MOBILIZATION / DEMOBILIZATION	635.11	-			
							1				1		LS	TRAFFIC CONTROL	641.10	-			
							4670				4670		LF	DURABLE 4 INCH WHITE LINE	646.400	9			
							4530				4530		LF	DURABLE 4 INCH YELLOW LINE	646.410	11			
							4670				4670		LF	TEMPORARY 4 INCH WHITE LINE	646.600	9			
							4530				4530		LF	TEMPORARY 4 INCH YELLOW LINE	646.610	11			
							93				93		EACH	LINE STRIPING TARGETS	648.76	-			
							30				30		LB	SEED	651.15	10			
							200				200		LB	FERTILIZER	651.18	36			
							1				1		TON	AGRICULTURAL LIMESTONE	651.20	-			
							1				1		TON	HAYMULCH	651.25	-			
							200				200		CY	TOPSOIL	651.35	22			
							133				133		SF	TRAFFIC SIGNS, TYPE A	675.20	-			
														BEGIN OPTION AA					
							330				330		LF	FLANGED CHANNEL SIGN POST	675.301	-			
							330				330		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
														END OPTION AA					

PROJECT NAME: DOVER
 PROJECT NUMBER: HES 0106(5)
 FILE NAME: 05c320quant.xls PLOT DATE: 04/11/2007
 PROJECT MANAGER: SDW DRAWN BY: MBL
 DESIGNED BY: MBL CHECKED BY: JLS
 QUANTITY SHEET #1 SHEET 3 OF 18