STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET# 2

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																				REMARKS	SIGN DETAIL	
												FLANGED CHANNEL			SQUARE STEEL (In)					TUBULAR ALUMINUM Ø (IN)			TUBULAR STEEL Ø (IN)				W-SHAPE STEEL						
		EACH	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POST	(LB / FT)			1.75	2.00	2.50	ANCHOR	SLEEVE	3.00	4.00	4.0 MOD	FOUNDATION	3.00	3.50	4.00	5.00	FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME REQUIRED			
															(LB / FT)					(LB / FT)				(LB / FT)				24"	30"					
												1.12	2.00	3.00	1.68	2.16	3.35			1.30	1.70	1.70		7.60	9.00	10.80	14.60							
	OPTION ITEMS																																	
21+23.7, LT.		1	30.0	30.0	6.3						1			X		X 16.0																W1-2mb R	17	
	SPEED LIMIT 25	1	18.0	18.0	2.3																												W13-1		E-155
25+75.0, RT.		1	30.0	30.0	6.3						1			X		X 16.0																W1-10 R	17	
	SPEED LIMIT 25	1	18.0	18.0	2.3																												W13-1		E-155
26+30.0, RT.	SPEED LIMIT 35	1	24.0	30.0	5.0						1			X		X 16.0																R2-1		E-142
	DO NOT PASS	1	24.0	30.0	5.0																												R4-1		E-141
29+27.9, LT.	BRICKYARD ROAD						1				1			X		X 14.0																SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		E-123
	STOP	1	30.0	30.0	6.3																												R1-1		E-143
33+15.0, LT.		1	30.0	30.0	6.3						1			X		X 16.0																W1-10 L	17	
	SPEED LIMIT 25	1	18.0	18.0	2.3																												W13-1		E-155
	SHEET 2 TOTALS				42.1	0.0	1							75.0		75.0																		
	SHEET 1 TOTALS				91.0	0.0	2							255.0		255.0																		
	TOTALS			SF 133.0 ~~133.1~~	SF 0	EA. 3	SF .	XXXXXXXXXX XXXXXXXXXX XXXXXXXXXX				FT .	FT .	FT ~~330~~	FT .	FT ~~330~~	FT .	XXXXX XXXXX XXXXX XXXXX EA .		LB .	LB .	LB .		LB .	LB .	LB .	LB .	EA .	EA .	LB .				
								REMOVED 16 SIGNS				FT ~~330~~ 318			FT 330					LB .			EA.	LB .										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY & TRAFFIC SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: DOVER
PROJECT NUMBER: HES 0106(5)

FILE NAME: d05c320frm.dgn
PROJECT MANAGER: SDM
DESIGNED BY: MBL
TRAFFIC SIGN SUMMARY SHEET #2

PLOT DATE: 01/24/2007
DRAWN BY: MBL
CHECKED BY: JLS
SHEET 16 OF 18