



	<b>ROAD WORK AHEAD</b>	<b>ROAD WORK 500 FT</b>	<b>END ROAD WORK</b>	<b>ROAD WORK NEXT 1/2 MILE</b>
BEGIN PROJECT	2	2	1	1
END PROJECT	2	2	1	1
SIDE ROADS	6	0	3	0
TOTAL	10	4	5	2

LEGEND  
 RWA = ROAD WORK AHEAD  
 RW500 = ROAD WORK 500 FT  
 ERW = END ROAD WORK  
 RWN = ROAD WORK NEXT 1/2 MILE

### CONSTRUCTION APPROACH SIGNING

NOT TO SCALE  
 SEE STD E-100 FOR SIGN PLACEMENT

- NOTES:
1. CONSTRUCTION APPROACH SIGNING SHALL NOT INTERFERE OR BLOCK VISIBILITY OF EXISTING TRAFFIC CONTROL DEVICES.
  2. PAYMENT FOR CONSTRUCTION APPROACH SIGNING WILL BE MADE UNDER PAY ITEM 641.10

PROJECT NAME:	DOVER
PROJECT NUMBER:	HES 0106(5)
FILE NAME:	d05c320frm.dgn
PLOT DATE:	04/11/07
PROJECT LEADER:	SDM
DRAWN BY:	MBL
DESIGNED BY:	MBL
CHECKED BY:	JLS
<b>CONSTRUCTION APPROACH SIGNING</b>	SHEET 18 OF 18