

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FNAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													END OPTION CC					
						1				1		EACH	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.20				
						1				1		EACH	PRECAST REINFORCED CONCRETE MANHOLE WITH CAST IRON COVER	604.21				
						1				1		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40				
						50				50		LF	6 INCH UNDERDRAIN PIPE	605.10				
						2				2		LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20				
							5			5		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
						55				55		CY	STONE FILL, TYPE II	613.11				
						96				96		LF	VERTICAL GRANITE CURB	616.21				
						149				149		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
						4				4		EACH	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53				
						4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
						130				130		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						80				80		LF	TEMPORARY TRAFFIC BARRIER	621.90				
						24				24		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
								520		520		HR	EMPLOYEE TRAINEESHIP	634.10				
						1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
						1				1		LS	TRAFFIC CONTROL	641.10				
						410				410		LF	4 INCH YELLOW LINE	646.21				
						12				12		LF	24 INCH STOP BAR	646.26				
						160				160		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							180			180		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
							360			360		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							10			10		LB	SEED	651.15				
							30			30		LB	FERTILIZER	651.18				
							1			1		TON	AGRICULTURAL LIMESTONE	651.20				
							1			1		TON	HAY MULCH	651.25				
							20			20		CY	TOPSOIL	651.35				
							30			30		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN	652.10				
							150			150		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							290			290		SY	TEMPORARY EROSION MATTING	653.20				
							10			10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
							1			1		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
							3			3		EACH	FILTER BAG	653.45				
						120				120		LF	BARRIER FENCE	653.50				
						550				550		LF	PROJECT DEMARCATON FENCE	653.55				

PROJECT NAME: MIDDLEBURY-WEYBRIDGE

PROJECT NUMBER: BHO 1445(33)

FILE NAME: z06j086quant2.dgn  
PROJECT LEADER: M.D.SARGENT  
DESIGNED BY: J.BICJA

PLOT DATE: 9/20/2011  
DRAWN BY: J.B.McQUAID  
CHECKED BY: S.T.JAMES  
SHEET 9 OF 66



HTA PROJECT NO. 904217 MODEL Notes

**QUANTITY SHEET #2**