

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						100					100		LF	BEGIN OPTION BB 18" CAAP .075 (2-2/3 X 1/2)	601.0216				
						100					100		LF	18" PCCSP .079 (2-2/3 X 1/2)	601.0416				
						100					100		LF	18" CPEP	601.0915				
														END OPTION BB					
									15		15		CY	REBUILT STONE MASONRY	602.35				
						3					3		EACH	SANITARY SEWER MANHOLE	604.22				
						1					1		EACH	PRECAST REINFORCED CONCRETE PIPE DI WITH CAST IRON GRATE (4 FT. DIA.)	604.25				
						1					1		EACH	PRECAST REINFORCED CONCRETE PIPE DI WITH CAST IRON GRATE (5 FT. DIA. WITH 2 GRATES)	604.25				
						1					1		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42				
								1			1		MGAL	DUST CONTROL WITH WATER	609.10				
						20					20		CY	STONE FILL, TYPE I	613.10				
						205					205		CY	STONE FILL, TYPE II	613.11				
						160					160		LF	VERTICAL GRANITE CURB	616.21				
						114					114		LF	REMOVAL OF EXISTING CURB	616.41				
						24					24		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10				
						32					32		SF	DETECTABLE WARNING SURFACE	618.30				
						3					3		EACH	BOLLARDS	619.14				
						48					48		LF	CHAIN-LINK FENCE, 4 FEET	620.11				
						1					1		EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 4 FEET	620.20				
						70					70		LF	REMOVING AND RESETTNG FENCE	620.50				
						30					30		LF	REMOVAL OF EXISTING FENCE	620.55				
						190					190		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
						50					50		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215				
						3					3		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
						220					220		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						85					85		LF	PVC SEWER PIPE (10" DIA.)	628.35				
						25					25		LF	PVC SEWER PIPE (8" DIA.)	628.35				
						1					1		LS	TRANSFER TO NEW SYSTEM, SANITARY SEWER	628.42				
						2					2		EACH	ADJUST ELEVATION OF VALVE BOX	629.20				
						5					5		TON	CRUSHED STONE BEDDING	629.54				
						500					500		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							520				520		HR	EMPLOYEE TRAINEESHIP	634.10				
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						850					850		LF	4 INCH WHITE LINE	646.20				
						850					850		LF	4 INCH YELLOW LINE	646.21				

PROJECT NAME:	BARRE TOWN	PLOT DATE:	27-SEP-2012
PROJECT NUMBER:	BRF 6100(7)	DRAWN BY:	R. PELLETT
FILE NAME:	s06j002excel.dgn	CHECKED BY:	T. FILLBACH
PROJECT LEADER:	J. LACROIX	DESIGNED BY:	T. FILLBACH
QUANTITY 2		SHEET	8 OF 70