

QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						20					20		LF	24 INCH STOP BAR	646.26				
								310			310		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								60			60		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								112			112		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								30			30		LB	SEED	651.15				
								10			10		LB	SEED, WINTER RYE	651.17				
								150			150		LB	FERTILIZER	651.18				
								0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20				
								0.5			0.5		TON	HAY MULCH	651.25				
								50			50		CY	TOPSOIL	651.35				
								120			120		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								40			40		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								40			40		SY	TEMPORARY EROSION MATTING	653.20				
								15			15		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								2			2		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
								250			250		LF	BARRIER FENCE	653.50				
								450			450		LF	PROJECT DEMARCATION FENCE	653.55				
						12.5					12.5		SF	TRAFFIC SIGNS, TYPE A	675.20				
						70					70		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
						5					5		EACH	REMOVING SIGNS	675.50				
						5					5		EACH	ERECTING SALVAGED SIGNS	675.60				
									249		249		LF	SPECIAL PROVISION (BRIDGE RAILING, GALVANIZED METAL HAND RAILING/CONCRETE PARAPET COMBINATION)	900.640				
						1					1		LS	SPECIAL PROVISION (MAINTENANCE OF EXISTING WASTEWATER FLOWS)	900.645				
									1		1		LS	SPECIAL PROVISION (SEWER MAIN ON BRIDGE 10")	900.645				
						1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				
						1					1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
						1					1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
						30					30		SF	SPECIAL PROVISION (RETAINING WALL)	900.670				
						290					290		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: BARRE TOWN
 PROJECT NUMBER: BRF 6100(7)
 FILE NAME: s06j002excel.dgn
 PROJECT LEADER: J. LACROIX
 DESIGNED BY: T. FILLBACH
 QUANTITY 3
 PLOT DATE: 27-SEP-2012
 DRAWN BY: R. PELLETT
 CHECKED BY: T. FILLBACH
 SHEET 9 OF 70