QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

UTILITY	EMPLOYEE TRAINEESHIP	FULL C.E.	EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					1	1	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	
				50		50	CY	STONE FILL, TYPE II	613.11	EST
					111	111	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	
					49	49	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	
					15	15	SF	DETECTABLE WARNING SURFACE	618.30	
					124.6	124.6	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	
					2	2	EA	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53	
					4	4	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
					49	49	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	
					250	250	LF	TEMPORARY TRAFFIC BARRIER	621.90	
1						1	EA	GATE VALVE WITH VALVE BOX	629.27	
					400	400	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
					600	600	HR	FLAGGERS	630.15	EST
		1				1	LS	FIELD OFFICE, ENGINEERS	631.10	
		1				1	LS	TESTING EQUIPMENT, CONCRETE	631.16	
		1				1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	
		1				1	LS	TESTING EQUIPMENT, PROTECTIVE COATINGS	631.18	
		1				1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	
	520					520	HR	EMPLOYEE TRAINEESHIP	634.10	
					1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
					1	1	LS	TRAFFIC CONTROL	641.10	
					2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
					230	230	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	
					520	520	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	
					5	5	LF	DURABLE 12 INCH WHITE LINE, THERMOPLASTIC	646.462	
					17	17	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	
					60	60	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	
					150	150	SF	PAVEMENT MARKING MASK	646.86	EST
				125		125	SY	GEOTEXTILE UNDER STONE FILL	649.31	EST
			52			52	SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	
			165			165	SY	GEOTEXTILE FOR FILTER CURTAIN	649.61	2
					20	20	LB	SEED	651.15	EST
					125	125	LB	FERTILIZER	651.18	EST
					1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST
					10	10	CY	TOPSOIL	651.35	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET (2)

PROJECT NAME: MONTPELIER
PROJECT NUMBER: BHF 6400(31)

CHA
CLOUGH HARBOUR & ASSOCIATES LLP

FILE NAME: $FILES$
PROJECT MANAGER: SUSAN SCRIBNER
DESIGNED BY: D. D'AMATO
BRIDGE DESIGN SUPERVISOR: P. HALSTEAD

PLOT DATE: 10/12/2009
DRAWN BY: D. D'AMATO
CHECKED BY: P. PERKINS
SHEET 4 OF 63

FILE NAME =k:\14506\mstn\plans\zs14506_qua.dgn
DATE/TIME =10/12/2009
USER =2552