QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

UTILITY	EMPLOYEE TRAINEESHIP	FULL C.E.	EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			1			1	LS	EPSC PLAN	652.10	
			350			350	HR	MONITORING EPSC PLAN	652.20	EST
			1			1	LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	
			350			350	SY	TEMPORARY EROSION MATTING	653.20	EST
			150			150	CY	VEHICLE TRACKING PAD	653.35	
			185			185	LF	PROJECT DEMARCATION FENCE	653.55	3
					85.5	85.5	SF	TRAFFIC SIGN, TYPE A	675.20	
					176	176	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	
					11	11	EA	REMOVING SIGNS	675.50	
					6	6	EA	ERECTING SALVAGED SIGNS	675.60	
					1	1	EA	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40	
				125		125	CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS A LOW CEMENT)	900.608	
				100		100	EA	SPECIAL PROVISION (THROUGH TRUSS RIVET REPLACEMENT)	900.620	EST
1						1	LS	SPECIAL PROVISION (WATER MAIN ON BRIDGE) (8")	900.645	
					1	1	LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650	
					1	1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	
					170	170	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	2

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET (3)

PROJECT NAME: MONTPELIER
PROJECT NUMBER: BHF 6400(31)

CHA
CLOUGH HARBOUR & ASSOCIATES LLP

FILE NAME: $FILES$
PROJECT MANAGER: SUSAN SCRIBNER
DESIGNED BY: D. D'AMATO
BRIDGE DESIGN SUPERVISOR: P. HALSTEAD

PLOT DATE: 10/12/2009
DRAWN BY: D. D'AMATO
CHECKED BY: P. PERKINS
SHEET 5 OF 63

FILE NAME =k:\14506\mstn\plans\zs14506_quo.dgn
DATE/TIME =10/12/2009
USER =2552