STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET

CURB

BEGIN STATION	END STATION	POSITION LEFT FT	POSITION RIGHT FT	REMARKS
ITEM 616.28 CAST-IN-PLACE CONCRETE CURB, TYPE B				
14+02.3	14+17.3	20		
14+07.3	14+17.3		10	
15+88.8	16+28.0	45		
15+88.8	16+16.3		36	
SUBTOTAL (LT & RT)			111	
ROUNDING			-	
TOTAL			111	

SIDEWALK

BEGIN STATION	END STATION	POSITION LEFT SY	POSITION RIGHT SY	REMARKS
ITEM 618.10 PORTLAND CEMENT CONCRETE SIDEWALK, 5 IN				
14+02.3	14+17.3	12		
15+88.8	16+28.0	28		
16+07.8	16+16.3		9	
SUBTOTAL		49		
ROUNDING		-		
TOTAL		49		

DETECTABLE WARNING SURFACE

BEGIN STATION	END STATION	POSITION LEFT SF	POSITION RIGHT SF	REMARKS
ITEM 618.30 DETECTABLE WARNING SURFACE				
14+02.5		15		
SUBTOTAL		15		
ROUNDING		-		
TOTAL		15		

GUARD RAIL

BEGIN STATION	END STATION	POSITION LEFT FT	POSITION RIGHT FT	END TREATMENT BEGIN EA	END TREATMENT END EA
ITEM 621.21 HD STEEL BEAM GUARDRAIL, GALVANIZED					
14+02.5	14+18.0		44.5*		
14+08.0	14+17.0	12.8*			
END ROUNDED W-BEAM END SECTION FOR GUARDRAIL AT BEGIN OF EXISTING BRIDGE PEDESTRIAN RAILING					
15+88.0	16+05.0		32.0*		
15+88.0	16+19.5	35.3*			
BEGIN ROUNDED W-BEAM END SECTION FOR GUARDRAIL AT END OF EXISTING BRIDGE PEDESTRIAN RAILING					
SUBTOTAL (LT & RT)		124.6			
ROUNDING		-			
TOTAL		124.6			
ITEM 621.53 TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL					
14+18.0	14+20.0 RT				1
CONNECT TO BRIDGE RAIL AT STA. 14+20.0. SEE STD. G-16 FOR DETAILS.					
15+86.0	15+88.0 RT			1	
CONNECT TO BRIDGE RAIL AT STA. 15+86.0. SEE STD. G-16 FOR DETAILS.					
SUBTOTAL (BEGIN & END)					2
ROUNDING					-
TOTAL					2
ITEM 621.60 ANCHOR FOR STEEL BEAM RAIL					
14+02.5 RT				1	
15+97.0 LT				1	
16+00.0 RT					1
16+12.0 LT					1
SUBTOTAL (BEGIN & END)					4
ROUNDING					-
TOTAL					4

* PAY LENGTH INCLUDES ROUNDED W-BEAM END SECTION(S) AND PAYMENT FACTORS. SEE STD. G-1 AND G-1D FOR DETAILS.

UNDERDRAIN

BEGIN STATION	END STATION	TYPE	POSITION	DIA. IN	LENGTH FT	TRENCH EARTH CF	TRENCH ROCK CF	GRAN BKFILL CF	FB EA	MKR PST EA

PROJECT NAME: **MONTPELIER**
PROJECT NUMBER: **BHF 6400(31)**

FILE NAME: **14506_ItemDetail.xls**
PROJECT LEADER: **SUSAN SCRIBNER**
DESIGNED BY: **J. PARKER**
ITEM DETAIL SHEET

PLOT DATE: **6/26/2008**
DRAWN BY: **J. PARKER**
CHECKED BY: **D. GOZALKOWSK**
SHEET **11** OF **63**