

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	EROSION CONTROL	BRIDGE	ALT. A	ALT. B	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				1						1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
				25						25		CY	COMMON EXCAVATION	203.15				
				120						120		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
				1						1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
					1					1		LS	COFFERDAM (ABUTMENT NO. 1)	208.40				
				35						35		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
				10						10		CY	SUBBASE OF GRAVEL	301.15				
				10						10		CY	AGGREGATE SURFACE COURSE	401.10				
				1						1		CWT	EMULSIFIED ASPHALT	404.65				
				1						1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
						112000				112000		LB	STRUCTURAL STEEL, ROLLED BEAM	506.50				
						800				800		LB	STRUCTURAL STEEL	506.60				
						120				120		LB	REINFORCING STEEL, LEVEL I	507.11				
						28				28		LF	DRILLING AND GROUTING DOWELS	507.16				
						7				7		GAL	WATER REPELLENT, SILANE	514.10				
						10				10		MFBM	STRUCTURAL LUMBER AND TIMBER, UNTREATED	522.20	EST.			
						15				15		MFBM	STRUCTURAL LUMBER AND TIMBER, TREATED	522.25	EST.			
						5				5		MFBM	NONSTRUCTURAL LUMBER, UNTREATED	522.30	EST.			
				14						14		LF	JOINT SEALER, HOT POURED	524.11				
						2				2		CY	CONCRETE, CLASS B	541.25				
						2				2		CY	CONTROLLED DENSITY (FLOWABLE) FILL	541.45				
						5				5		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS I	580.13	EST.			
						5				5		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS II	580.14	EST.			
						5				5		CY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS III	580.15	EST.			
				1						1		MGAL	DUST CONTROL WITH WATER	609.10				
				25						25		CY	STONE FILL, TYPE I	613.10				
				200						200		CY	STONE FILL, TYPE III	613.12				
				4						4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
				245						245		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
				40						40		HR	FLAGGERS	630.15	EST.			
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
				1						1		LS	MOBILIZATION/DEMOLITION	635.11				
				1						1		LS	TRAFFIC CONTROL	641.10				
				14						14		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17				
				275						275		SY	GEOTEXTILE UNDER STONE FILL	649.31				
					25					25		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
					60					60		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				

PROJECT NAME:	CHARLOTTE
PROJECT NUMBER:	BHO 1445(34)
FILE NAME: z06j088qs.dgn	PLOT DATE: 09/12/2012
PROJECT LEADER: M.A. COLGAN	DRAWN BY: E.A. FIALA
DESIGNED BY: E.A. FIALA	CHECKED BY: B.O. CRONIN
QUANTITY SHEET #1	SHEET 5 OF 55

