

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	EROSION CONTROL	BRIDGE	ALT. A	ALT. B	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					10					10		LB	SEED	651.15				
					50					50		LB	FERTILIZER	651.18				
					1					1		TON	AGRICULTURAL LIMESTONE	651.20				
					1					1		TON	HAY MULCH	651.25				
					14					14		CY	TOPSOIL	651.35				
					275					275		SY	GRUBBING MATERIAL	651.40				
					330					330		LF	PROJECT DEMARCATION FENCE	653.55				
				4						4		EACH	DECIDUOUS TREES (SORBUS DECORA)(B& B)(3 IN)	656.30				
						1				1		LS	TIMBER PAINTING, ENVIRONMENTAL PROTECTION	660.10				
						1				1		LS	TIMBER PAINTING, FIRE RETARDANT	660.20				
						1				1		LS	TIMBER PAINTING, INSECTICIDE/FUNGICIDE	660.30				
						235				235		SY	METAL ROOFING	661.10				
				68						68		SF	TRAFFIC SIGNS, TYPE A	675.20				
				180						180		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
				7						7		EACH	REMOVING SIGNS	675.50				
				1						1		EACH	ERECTING SALVAGED SIGNS	675.60				
						5				5		CY	SPECIAL PROVISION (GROUT BAGS)	900.608				
						8				8		EACH	SPECIAL PROVISION (BEARING DEVICE ASSEMBLY, PREFORMED FABRIC PAD)	900.620				
						10				10		EACH	SPECIAL PROVISION (WOOD EPOXY REPAIRS)	900.620				
				240						240		LF	SPECIAL PROVISION (HD STEEL BEAM GUARDRAIL, WEATHERING) (WOOD POSTS)	900.640				
				1						1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
				1						1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
				10						10		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				
													BEGIN ALTERNATE A (IN-PLACE REHABILITATION)					
							1			1		LS	SHORING SUPERSTRUCTURE	502.10				
							1			1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
							1			1		LS	SPECIAL PROVISION (REHABILITATING COVERED BRIDGE SUPERSTRUCTURE)	900.645				
													END ALTERNATE A (IN-PLACE REHABILITATION)					
													BEGIN ALTERNATE B (RELOCATED REHABILITATION)					
								1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
								1		1		LS	SPECIAL PROVISION (HANDLING, TRANSPORT, AND RE-ERECTION OF COVERED BRIDGE SUPERSTRUCTURE)	900.645				
								1		1		LS	SPECIAL PROVISION (REHABILITATING COVERED BRIDGE SUPERSTRUCTURE)	900.645				
													END ALTERNATE B (RELOCATED REHABILITATION)					

PROJECT NAME: CHARLOTTE
 PROJECT NUMBER: BHO 1445(34)
 FILE NAME: z06j088qs.dgn
 PROJECT LEADER: M.A. COLGAN
 DESIGNED BY: E.A. FIALA
 QUANTITY SHEET #2
 PLOT DATE: 09/12/2012
 DRAWN BY: E.A. FIALA
 CHECKED BY: B.O. CROWIN
 SHEET 6 OF 65

