



BATTERIES

The rechargeable batteries are of sealed lead calcium maintenance-free construction with a fully gelled electrolyte in a polypropylene case. These batteries will not leak or spill even if left upside down for extended periods of time.

ELECTRICAL SPECIFICATIONS

Nominal voltage	12 volts
Charging voltage	
Float	13.5 - 13.8 VDC
Cycle	14.4 - 14.8 VDC
Operating Temp. Range	
Discharge	-76° F to +122° F (-60° C to +50° C)
Charge	-4° F to +122° F (-20° C to +50° C)



PS12120



PS1270



PS12180



PS12350, PS12550

BATTERY FEATURES

- Long Life
- Completely Sealed
- Charge and Discharge in any Position
- Low Self Discharge
- Maintenance Free

SPECIFICATIONS

Model	Capacity	Terminal Type	Dimensions	Weight
	(20 hr. rate)			
PS1270	7 AH	Faston tab “.187” series	5.11 cm L x 10.03 cm H x 6.6 cm W 5.95" L x 3.95" H x 2.6" W	5.75 lbs. (2.61 kg)
PS12120	12 AH	Faston tab “.250” series	12.48 mm L x 5.97 mm H x 4.72 mm W 5.94" L x 3.70" H x 3.98" W	9.33 lbs. (4.24 kg)
PS12180	18 AH	Terminal posts w/5 mm nut & bolt connectors	18.11 cm L x 16.69 cm H x 7.59 cm W 7.13" L x 6.57" H x 2.99" W	13.2 lbs. (5.99 kg)
PS12350	35 AH	"L" blade w/.64 mm hole	19.69 cm L x 18.54 cm H x 12.95 cm W 7.75" L x 7.3" H x 5.1" W	24 lbs. (10.89 kg)
PS12550	55 AH	"L" blade w/6.4 mm hole at negative, 8.9 mm sq. cutout at positive	26.04 cm L x 22.23 cm H x 17.27 cm W 10.25" L x 8.75" H x 6.8" W	39 lbs. (17.69 kg)

Specifications are provided for information only and are believed to be accurate. However, no responsibility is assumed by Mammoth Fire Alarms, Inc. for their use. Specifications subject to change without notice. © 1999 All Rights Reserved