



TEMPORARY BRIDGE NOTES:

1. ALL TEMPORARY BRIDGE DETAILS NOT SHOWN SHALL BE DESIGNED AND FURNISHED BY THE CONTRACTOR FOR VAOT APPROVAL PER SECTION 528 OF THE SPECIFICATIONS.
2. THE WF36X230 BEAMS REQUIRED WILL BE PROVIDED BY THE AGENCY. HOWEVER THE CONTRACTOR MUST PROVIDE MEANS FOR BOTH LOADING AND TRANSPORTING THE BEAMS TO THE BRIDGE SITE. THE BEAMS ARE LOCATED AT THE VAOT MAINTENANCE ROYALTON DISTRICT 4 SITE ON VT 107. THE CONTRACTOR SHALL CONTACT TAMMY ELLIS, GENERAL MAINTENANCE MANAGER DIST. 4 (802-296-5568), PROVIDING ONE WEEK NOTICE OF INTENT TO REMOVE THE BEAMS.
3. CURBS SHALL BE 6X10 NO. 2 GRADE SOUTHERN PINE CUT AT A MINIMUM LENGTH OF 8 FEET. DECK PANELS SHALL BE LAMINATED 2X6 SOUTHERN YELLOW PINE NO. 2 GRADE LUMBER. ALL LUMBER SHALL BE TYPE II PRESERVATIVE TREATED IN ACCORDANCE WITH SUPPLEMENTAL SPEC. SECTION 726 OF THE SPECIFICATIONS. EXCEPT AS NOTED, ALL LUMBER SHALL BE DRESSED SIZE AND FINISH.
4. ALL BOLTS, NUTS, AND WASHERS SHALL BE IN ACCORDANCE WITH ASTM A307 REQUIREMENTS.
5. SEE THE SPECIAL PROVISIONS SECTION 528 FOR ALL WORK AND PAYMENT CONCERNING PAY ITEM 528.10 ONE-WAY TEMPORARY BRIDGE (MOD.).

PROJECT NAME:	RANDOLPH
PROJECT NUMBER:	BHO_1444(50)
FILE NAME:	s06j094dt1.dgn
PROJECT LEADER:	J. WEAVER
DESIGNED BY:	J. IBEI
TEMPORARY BRIDGE DETAILS SHEET:	SHEET J2 OF 18
PLOT DATE:	3/27/06
DRAWN BY:	J. IBEI
CHECKED BY:	J. WEAVER