

STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	VT11 - BRIDGE NO. 45	VT11 - BRIDGE NO. 46	US5 - BRIDGE NO. 33	TH4 - BRIDGE NO. D19	US5 - BRIDGE NO. 8	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				1							1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
						733	675	400	622		2430		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
						3	4	3	4		14		CWT	EMULSIFIED ASPHALT	404.65				
						165	338	175	296		974		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	406.27				
						1	1	1	1		4		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	406.29				
				1							1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
					35	30	55	25	50		195		GAL	WATER REPELLENT, SILANE	514.10				
					120	63		156			339		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
						507	1800	897	1556		4760		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
						126		60			186		LF	JOINT SEALER, HOT POURED	524.11				
						507	1800	897	1556		4760		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
						10	40	40	40		130		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
						5	5	30	5		45		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
						3	3	3	3		12		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
						4563	16201	8070	14001		42835		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
						3	3	3	3		12		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
					120	120	240		220		700		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
					410	410	1470	40	1270		3600		HR	FLAGGERS	630.15				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
				1							1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
								1			1		LS	TRAFFIC CONTROL (TH 4 - BRIDGE NO. D19)	641.10				
							1				1		LS	TRAFFIC CONTROL (US 5 - BRIDGE NO. 33)	641.10				
									1		1		LS	TRAFFIC CONTROL (US 5 - BRIDGE NO. 8)	641.10				
					1						1		LS	TRAFFIC CONTROL (VT 11 - BRIDGE NO. 45)	641.10				
						1					1		LS	TRAFFIC CONTROL (VT 11 - BRIDGE NO. 46)	641.10				
					1	1	2	2	2		8		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						1740	2700	780	2160		7380		LF	4 INCH WHITE LINE	646.20				
						1740	2700	780	2160		7380		LF	4 INCH YELLOW LINE	646.21				
						1740	2700	780	2160		7380		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
						3480	5400	1340	4320		14540		LF	TEMPORARY 4 INCH WHITE LINE, TYPE II TAPE	646.601				
						1740	2700	780	2160		7380		LF	TEMPORARY 4 INCH YELLOW LINE	646.610				
						21	45	29	37		132		EACH	LINE STRIPING TARGETS	646.76				

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: BHF MEMB(21)

FILE NAME: ...\\04_quantity sheets.dgn	PLOT DATE: 10/13/2009
PROJECT LEADER: G. BOGUE	DRAWN BY: E. ALLING
DESIGNED BY: S. BURBANK	CHECKED BY: S. BURBANK
QUANTITY SHEET	SHEET 4 OF 34

