

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	AARDOT 837-138R ROADWAY	AARDOT 837-138R RAILROAD	AARDOT 837-139X ROADWAY	AARDOT 837-139X RAILROAD	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							10		50		60		CY	COMMON EXCAVATION	203.15	4.2			
							15				15		CY	TRENCH EXCAVATION OF EARTH	204.20	4.3			
							1		1		2		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
							280		280		560		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	4.4			
							2.5		2.5		5		TON	AGGREGATE SHOULDERS	402.12	EST.			
							4		6		10		CWT	EMULSIFIED ASPHALT	404.65	1			
						1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
							1				1		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18	-			
							1				1		EACH	YIELDING MARKER POSTS	619.17	-			
							50		50		100		HR	FLAGGERS	630.15	EST.			
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							320		620		940		LF	DURABLE 4 INCH YELLOW LINE	646.410	26			
							2		2		4		EACH	DURABLE RAILROAD CROSSING SYMBOL	646.510	-			
							10		10		20		LB	SEED	651.15	EST.			
							88		87		175		LB	FERTILIZER	651.18	EST.			
							0.35		0.35		0.7		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
							0.35		0.35		0.7		TON	HAY MULCH	651.25	EST.			
							45		45		90		CY	TOPSOIL	651.35	EST.			
							160		160		320		LF	BARRIER FENCE	653.50	9			
							280		280		560		LF	PROJECT DEMARCATION FENCE	653.55	20			
							14.2		41.2		55.4		SF	TRAFFIC SIGNS, TYPE A	675.20	-			
							28		112		140		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
							6		6		12		EACH	REMOVING SIGNS	675.50	-			
								10		10	20		CY	SPECIAL PROVISION (RAILROAD BALLAST)	900.608	EST			
								1			1		EACH	SPECIAL PROVISION (BALLASTED TURNOUTS, INSULATED)	900.620	-			
								30		30	60		EACH	SPECIAL PROVISION (REMOVAL AND REPLACEMENT OF CROSS TIES)	900.620	EST			
								1			1		LS	SPECIAL PROVISION (RAIL-HIGHWAY CROSSING ACTIVE WARNING SYSTEM)(AARDOT 837-138R)	900.645	-			
									1		1		LS	SPECIAL PROVISION (RAIL-HIGHWAY CROSSING ACTIVE WARNING SYSTEM)(AARDOT 837-139X)	900.645	-			
								1			1		LS	SPECIAL PROVISION (RECONSTRUCT RAIL-HIGHWAY CROSSING)(AARDOT 837-138R)	900.645	-			
									1		1		LS	SPECIAL PROVISION (RECONSTRUCT RAIL-HIGHWAY CROSSING)(AARDOT 837-139X)	900.645	-			
								1			1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, RAIL-HIGHWAY CROSSING)(AARDOT 837-138R)	900.645	-			
									1		1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, RAIL-HIGHWAY CROSSING)(AARDOT 837-139X)	900.645	-			
								0.5		0.5	1		LU	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC) (N.A.B.I.)	900.650	-			
							1		1		2		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650	-			
							1		1		2		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-			
							70		160		230		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	10.1			

PROJECT NAME: PITTSFORD
PROJECT NUMBER: STP 2033(21)

FILE NAME: ...\\plotfiles\03 quantity.dgn PLOT DATE: 6/7/2013
PROJECT LEADER: G. EDWARDS DRAWN BY: DKG
DESIGNED BY: STANTEC CHECKED BY: KJR
QUANTITY SHEET SHEET 7 OF 21

