

# COMPOSITE QUANTITY SHEET 1

BRF 3000(19) RUTLAND CITY						BRF 3000(16) RUTLAND CITY						SUMMARY OF ESTIMATED QUANTITIES				DETAILED SUMMARY OF QUANTITIES			
UTILITIES - BID ITEMS	EROSION CONTROL	BRIDGE	TRAINING	FULL C.E.	ROADWAY	UTILITIES - BID ITEMS	EROSION CONTROL	BRIDGE	TRAINING	FULL C.E.	ROADWAY	GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
											1	1	LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (BRF 3000(16))	201.10				
					1							1	LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (BRF 3000(19))	201.10				
					3800						4760	8560	CY	COMMON EXCAVATION	203.15				
											150	150	CY	SOLID ROCK EXCAVATION	203.16				
		200						3290				3490	CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
					1250							1250	CY	EARTH BORROW	203.30				
					1300	12					860	2172	CY	SAND BORROW	203.31				
								1030				1030	CY	GRANULAR BORROW	203.32				
235					920	12					160	1327	CY	TRENCH EXCAVATION OF EARTH	204.20				
11					8	10					28	57	CY	TRENCH EXCAVATION OF ROCK	204.21				
					1						1	2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
		315						240			200	755	CY	STRUCTURE EXCAVATION	204.25				
		430						850			110	1390	CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
		240						750				990	CY	COFFERDAM EXCAVATION, EARTH	208.30				
		30						90				120	CY	COFFERDAM EXCAVATION, ROCK	208.35				
								1				1	LS	COFFERDAM (ABUTMENT 1) (BR 2)	208.40				
		1										1	LS	COFFERDAM (PIER 1) (BR 17)	208.40				
					500						410	910	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
					2300						4060	6360	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
											60	60	CY	AGGREGATE SURFACE COURSE	401.10				
					1						1	2	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
					1300			155			1316	2771	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30				
					1						1	2	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31				
		16			1			414				431	CY	CONCRETE, HIGH PERFORMANCE CLASS A	501.33				
		528						586				1114	CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
		0.5						0.5				1	LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10				
								325				325	LF	STEEL PILING, HP 12 X 84	505.165				

FILE NAME = W:\P\Projects\14\14000\MSTN\08\1096\ecmsul\ants\208\096cmptqm.dgn  
 DATE/TIME = 7/7/2014  
 USER = 4916

<b>COMPOSITE QUANTITY SHEET #1</b>	PROJECT NAME: RUTLAND CITY
	PROJECT NUMBER: BRF 3000(19) & BRF 3000(16)
PROJECT LEADER: M.D.S.	PLOT DATE: 7/7/2014
DESIGNED BY: D.M.D.	DRAWN BY: D.M.D.
DWG. NO.: CMPQTY-1	CHECKED BY: P.M.P.
	SHEET 4 OF 245