COMPOSITE QUANTITY SHEET 2

BRF 3000(19) RUTLAND CITY						BRF 3000(16) RUTLAND CITY						SUMMARY OF ESTIMATED QUANTITIES					DETAILED SUMMARY OF QUANTITIES		
UTILITIES - BID ITEMS	EROSION CONTROL	BRIDGE	TRAINING	FULL C.E.	ROADWAY	UTILITIES - BID ITEMS	EROSION CONTROL	BRIDGE	TRAINING	FULL C.E.	ROADWAY	GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
		2480										2480	LF	STEEL PILING, HP 14 X 102	505.19				
		770						2700				3470	LF	STEEL PILING, HP 14 X 117	505.20				
		3						2				5	EACH	DYNAMIC PILE LOADING TEST	505.45				
								510,190				510,190	LB	STRUCTURAL STEEL, PLATE GIRDER	506.55				
		31,530			3100			74,490				109,120	LB	REINFORCING STEEL, LEVEL I	507.11				
		15,125						105,210				120,335	LB	REINFORCING STEEL, LEVEL II	507.12				
								1				1	LS	SHEAR CONNECTORS (2325 - 7/8" X 7")	508.15				
								60				60	GAL	WATER REPELLENT, SILANE	514.10				
								81				81	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
		38						40				78	LF	BRIDGE EXPANSION JOINT, VERMONT	516.11				
								922				922	SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
		56						32				88	LF	JOINT SEALER, HOT POURED	524.11				
		425										425	LF	BRIDGE RAILING, GALVANIZED HDSB/FASCIA MOUNTED/STEEL TUBING	525.44				
		381										381	SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
								1				1	EACH	REMOVAL OF STRUCTURE (6190 SF - EST.) (BR 2)	529.15				
		1										1	EACH	REMOVAL OF STRUCTURE (3430 SF - EST.) (BR 17)	529.15				
		150			12							162	CY	REMOVAL OF CONCRETE OR MASONRY	529.25				
								5				5	EACH	BEARING DEVICE ASSEMBLY, HIGH LOAD MULTI-ROTATIONAL	531.15				
								10				10	EACH	BEARING DEVICE ASSEMBLY, STEEL REINFORCED ELASTOMERIC PAD	531.17				
					40							40	CY	CONCRETE, CLASS B	541.25				
		200										200	CY	CONCRETE, CLASS D	541.31				
					6	4					3	13	CY	CONTROLLED DENSITY (FLOWABLE) FILL	541.45				
														BEGIN OPTION AA					
					431							431	LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415				
					431							431	LF	18" RCP CLASS III	601.0815				
					431							431	LF	18" CPEP(SL)	601.2615				
														END OPTION AA					

COMPOSITE QUANTITY SHEET #2

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: BRF 3000(19) & BRF 3000(16)

PROJECT LEADER: M.D.S.
DESIGNED BY: D.M.D.
DWG. NO.: CMPQTY-2

PLOT DATE: 7/7/2014
DRAWN BY: D.M.D.
CHECKED BY: P.M.P.
SHEET 5 OF 245

FILE NAME = Y:\Projects\ANY\K2\20815\CADD\MSTN\08_@916\consultants\208_@916cmpquan.dgn
DATE/TIME = 7/7/2014
USER = 4916