

COMPOSITE QUANTITY SHEET 6

BRF 3000(19) RUTLAND CITY						BRF 3000(16) RUTLAND CITY						SUMMARY OF ESTIMATED QUANTITIES					DETAILED SUMMARY OF QUANTITIES		
UTILITIES - BID ITEMS	EROSION CONTROL	BRIDGE	TRAINING	FULL C.E.	ROADWAY	UTILITIES - BID ITEMS	EROSION CONTROL	BRIDGE	TRAINING	FULL C.E.	ROADWAY	GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
	275						200					475	SY	GEOTEXTILE FOR SILT FENCE	649.51				
	345						179					524	SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
	650						1022					1672	SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
					100		130					230	LB	SEED	651.15				
							100					100	LB	SEED, WINTER RYE	651.17				
	400						800					1200	LB	FERTILIZER	651.18				
	2						3					5	TON	AGRICULTURAL LIMESTONE	651.20				
	2						3					5	TON	HAY MULCH	651.25				
					400		820					1220	CY	TOPSOIL	651.35				
		150			100		1390					1640	SY	GRUBBING MATERIAL	651.40				
							1					1	LS	EPSC PLAN (BR 2)	652.10				
	1											1	LS	EPSC PLAN (BR 17)	652.10				
	100						350					450	HR	MONITORING EPSC PLAN	652.20				
							1					1	LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BR 2)	652.30				
												1	LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BR 17)	652.30				
	1800						1650					3450	SY	TEMPORARY EROSION MATTING	653.20				
	200											200	SY	PERMANENT EROSION MATTING	653.21				
	310						112					422	CY	VEHICLE TRACKING PAD	653.35				
	11											11	EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
	1											1	EACH	FILTER BAG	653.45				
	770						1110					1880	LF	BARRIER FENCE	653.50				
	1320						1429					2749	LF	PROJECT DEMARCATION FENCE	653.55				
											12	12	EACH	DECIDUOUS TREES (ACER SACCHARUM, 2 1/2"-3" CAL)	656.30				
					90						80	170	SF	TRAFFIC SIGNS, TYPE A	675.20				
					220						100	320	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
					19						22	41	EACH	REMOVING SIGNS	675.50				
											154	154	LF	WIRED CONDUIT (2")	678.23				

FILE NAME = W:\Projects\10454\10454.dwg
 DATE/TIME = 7/15/2014 4:49:16
 USER =

COMPOSITE QUANTITY SHEET #6	PROJECT NAME: RUTLAND CITY
	PROJECT NUMBER: BRF 3000(19) & BRF 3000(16)
PROJECT LEADER: M.D.S.	PLOT DATE: 7/15/2014
DESIGNED BY: D.M.D.	DRAWN BY: D.M.D.
DWG. NO.: CMPQTY-6	CHECKED BY: P.M.P.
	SHEET 9 OF 245