ITEM DETAIL SUMMARY SHEET #2

LOCATION			UNDERDRAIN				CURB	SIDEWALK			GUARDRAIL				UTILITIES								REMARKS
			204.20	605.10	605.20	605.95	616.28	618.10	618.11	618.30	621.20	621.737	621.60	621.80	204.20	604.22	604.56	628.28	629.24	629.27	629.29	629.35	
BEGIN STATION	END STATION	POS.	TRENCH EX. OF EARTH	6 IN. UND. PIPE	6 IN. UND. CAR. PIPE	UND. FLSH. BASIN	C.I.P.CONC CRB., TYPE B	PCC SW 5 IN	PCC SW 8 IN	DET. WARN. SURF.	S.B. GR. GALV.	GR. APP. SECT, GALV SB	ANCHOR FOR S.B. RAIL	R&D OF GR	TRENCH EX. OF EARTH	SAN. SEW. M.H.	C.I. COV. W/FRM.	D.I. PIPE C-L	D.I. PIPE C-L	G. V. WITH V. B.	REL. HYD.	TAP. SLV. WITH V. B.	
			CY	LF	LF	EACH	LF	SY	SY	SF	EACH	EACH	EACH	LF	CY	EACH	EACH	LF	LF	EACH	EACH	EACH	
TH 10 (RIPLEY ROAD/ DORR DRIVE)																							
9+91.4	10+63.1	LT	23.0	56.0	4.0	1																	SEE PLAN LAYOUT SHEET #2, AND TH 10 CROSS SECTIONS FOR LAYOUT AND INVERTS. SEE VTRANS' STD. SHEET D-30 FOR CONSTRUCTION DETAILS. EXCAVATION SHALL BE PAID AS TRENCH EXCAVATION OF EARTH. OUTLET UNDERDRAIN INTO DROP INLET AT STA 10+65.0.
10+65.6	12+05.0	LT	70.0	132.0	4.0	1																	SEE PLAN LAYOUT SHEET #2, AND TH 10 CROSS SECTIONS FOR LAYOUT AND INVERTS. SEE VTRANS' STD. SHEET D-30 FOR CONSTRUCTION DETAILS. EXCAVATION SHALL BE PAID AS TRENCH EXCAVATION OF EARTH. OUTLET UNDERDRAIN INTO DROP INLET AT STA 10+65.0.
12+82.9	13+54.7	LT					78.4																SEE VTRANS' STD. C-10, TYPICAL SECTIONS #1, AND TH 10 CROSS SECTIONS FOR INSTALLATION DETAILS AND CURB REVEAL TRANSITION NOTES.
13+34.1	13+34.1	RT													5.0				5.0		1		RELOCATE HYDRANT AS SHOWN ON PLAN LAYOUT SHEET #3.
SUBTOTALS			93.0	188.0	8.0	2	78.4	-	-	-	-	-	-	-	5.0	-	-	-	5.0	-	1	-	
SHEET 27 SUBTOTALS			139.0	370.0	4.0	1	629.8	397.9	26.6	20.0	183.0	4	4	409.6	228.0	5	5	507.3	91.6	2	-	2	
ROUNDING			-	-	-	-	1.8	2.1	3.4	-	-	-	-	0.4	-	-	-	2.7	0.4	-	-	-	
TOTALS			232.0	558.0	12.0	3	710.0	400.0	30.0	20.0	183.0	4	4	410.0	233.0	5	5	510	97.0	2	1	2	

CHA

ITEM DETAIL SUMMARY SHEET #2

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: BRF 3000 (19)

PROJECT LEADER: M.D.S.
DESIGNED BY: C.R.H.
DWG. NO.: IDS-1

PLOT DATE: 6/30/2014
DRAWN BY: C.R.H.
CHECKED BY: D.E.G.
SHEET 28 OF 245

FILE NAME = V:\Projects\ANY\K2\20815\CADD\MSTN\08_096\consultants\z08_096ids.dgn
DATE/TIME = 6/30/2014
USER = 4916