N

VT STATE PLANE GRID

SEE LAYOUT PLANS (SHEETS 33-36)
FOR PROPOSED DRAINAGE NOTES
(TYP.)

WETLAND A

24" CSMP PLUGGED

EXISTING R.O.W.

2'X2'

CZ

END PROJECT
BEGIN APPROACH
STA 14+00.00

END APPROACH
STA 15+00.00

EL JCT BOX

IP CAP2 UNREADABLE

COMB
II/10-2712

TH 10 (DORR DRIVE)

TO TH 8

MATCH LINE - UTILITY LAYOUT SHEET #2 - STA 11+00

EXISTING R.O.W.

13+00

14+00

12+00

HYD

HVCTRL

CONST.(T)

SLOPE(T)
CONST.(T)

REMOVE(T)

DRIVE(T)

RELOCATE HYDRANT
STA 13+34.1 RT

LIGHT POLES TO BE
RELOCATED BY OTHERS
(TYP.)

END TH10
POE STA 16+00.00

SANITARY SEWER MANHOLE,
WITH CAST IRON COVER
STA 11+44.8 RT

MHS

LL
SUBE

LL
SUBE

604.56 CAST IRON COVER WITH FRAME, SEWER
TH 10 STA 11+44.8 RT (1 EACH)

604.22 SANITARY SEWER MANHOLE
TH 10 STA 11+44.8 RT (1 EACH)

628.28 DUCTILE IRON PIPE, CEMENT-LINED (8")
TH 10 STA 11+00.0 TO STA 11+44.8 RT (52.8 LF)

629.24 DUCTILE IRON PIPE, CEMENT-LINED (8")
TH 10 STA 13+34.1 TO STA 13+34.1 RT (5.0 LF)

629.29 RELOCATE HYDRANT
TH 10 STA 13+34.1 RT (1 EACH)

NOTES:

1. SANITARY SEWER CONSTRUCTION SHALL BE IN CONFORMANCE WITH VTRANS STD. D-22 AND SECTIONS 604 AND 628 OF THE STANDARD SPECIFICATIONS.
2. WATER SYSTEM CONSTRUCTION SHALL BE IN CONFORMANCE WITH SECTION 629 OF THE STANDARD SPECIFICATIONS.

SEE REVISED SHEET 45A

20 0 20
SCALE IN FEET

CHA

UTILITY LAYOUT SHEET #3

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: BRF 3000 (19)

PROJECT LEADER: M.D.S.
DESIGNED BY: C.R.H.
DWG. NO.: UP-3

PLOT DATE: 6/30/2014
DRAWN BY: C.R.H.
CHECKED BY: D.E.G.
SHEET 45 OF 245

FILE NAME = V:\Projects\VNY\K2\26515\CADD\MSTN\08_@96\consultants\x08_@96bdr-up.dgn
DATE/TIME = 6/30/2014
USER = 4916