



Pipe not to be installed

DI at Stat 12+95 RT to be moved to new location, to be determined in the field. New outlet pipe to tie into existing 24" CMP utilized by CSJ. Remove existing DI as per plan.

DI at Stat 12+31 RT to be moved to new location determined by College Of Saint Josephs. 18" pipe to be installed from new DI location to DI at Stat 12+12 LT.

- 604.56 CAST IRON COVER WITH FRAME, SEWER  
TH 10 STA 11+44.8 RT (1 EACH)
- 604.22 SANITARY SEWER MANHOLE  
TH 10 STA 11+44.8 RT (1 EACH)
- 628.28 DUCTILE IRON PIPE, CEMENT-LINED (8")  
TH 10 STA 11+00.0 TO STA 11+44.8 RT (52.8 LF)
- 629.24 DUCTILE IRON PIPE, CEMENT-LINED (8")  
TH 10 STA 13+34.1 TO STA 13+34.1 RT (5.0 LF)
- 629.29 RELOCATE HYDRANT  
TH 10 STA 13+34.1 RT (1 EACH)

**NOTES:**

1. SANITARY SEWER CONSTRUCTION SHALL BE IN CONFORMANCE WITH VTRANS STD. D-22 AND SECTIONS 604 AND 628 OF THE STANDARD SPECIFICATIONS.
2. WATER SYSTEM CONSTRUCTION SHALL BE IN CONFORMANCE WITH SECTION 629 OF THE STANDARD SPECIFICATIONS.

20 0 20  
SCALE IN FEET



<b>UTILITY LAYOUT SHEET #3</b>	PROJECT NAME: RUTLAND CITY	PLOT DATE: 6/30/2014
	PROJECT NUMBER: BRP 3000 (19)	DRAWN BY: C.R.H.
	PROJECT LEADER: M.D.S.	CHECKED BY: D.E.G.
	DESIGNED BY: C.R.H.	SHEET 45A OF 245
	DWG. NO.: UP-3	

FILE NAME = I:\Projects\2014\BRP3000\BRP3000\BRP3000.dwg  
 DATE/TIME = 6/30/2014 4:56:16 PM  
 USER = CRH