STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS: EACH	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS: "A" (SF)	"B" (SF)	SALV SIGN	SALV TIS	EXIST POST: RETAIN	SALVAGE	NEW SIGN POSTS: NO. OF POSTS	FLANGED CHANNEL (LF) lb/ft: 1.1	2.0	3.0	SQUARE TUBE (LF) Ø (In): 1.8	2.0	2.5	SQUARE TUBE (LF) lb/ft: 1.88	2.42	3.35	ANCHOR	SLIP BASE	TUBULAR ALUMINUM (LF) Ø (In): 3.0	4.0	4.0 MOD	TUBULAR ALUMINUM (LF) lb/ft: 1.3	1.7	1.7	FOUNDATION	TUBULAR STEEL (LF) Ø (In): 3.0	3.5	4.0	5.0	TUBULAR STEEL (LF) lb/ft: 7.6	9.0	10.8	14.6	W-SHAPE STEEL FTG. SIZE: 24"	30"	W-SHAPE STEEL WEIGHT (LB)	W-SHAPE STEEL POST SIZE	RELOCATED SIGNS	REMARKS (SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK)	SIGN DETAIL: DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
TH-10:																																													
5+13.0, LT	R R	1	36	36	8.00						1					X		X																								SIGN ID CODE W10-1	X		
7+50.0, RT		1	36	36	9.00						2					X		X																								SIGN ID CODE W1-10L	X		
7+50.0, RT	30 M.P.H.	1	18	18	2.25																																				SIGN ID CODE W13-1P	X		
10+17.0, LT	Ripley Rd	1	42	12	3.50						1					X		X																								SIGN ID CODE D3-1		53	
10+71.0, RT	Dorr Dr / Clement Rd	1 1	36 42	12 12	3.00 3.50						1					X		X																								DOUBLE-SIDED SIGN, SIGN ID CODE D3-1 DOUBLE-SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		53 53	
	STOP	1	30	30	6.25																																				SIGN ID CODE R1-1	X		
10+73.5, RT		1	48	24	8.00						2					X		X																								SIGN ID CODE W1-6L	X		
10+75.0, RT		1	48	24	8.00						2					X		X																								SIGN ID CODE W1-6R	X		
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	LF 126	LF		EA.	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB														
	TOTALS				SF 51.50	SF	EA.	SF				LF			LF 126					LB			EA.	LB				EA.	EA.	LB												

TRAFFIC SIGN SUMMARY SHEET #1

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: BRF 3000 (19)

PROJECT LEADER: M.D.S.
DESIGNED BY: C.R.H.
DWG. NO.: TSS-1

PLOT DATE: 6/30/2014
DRAWN BY: C.R.H.
CHECKED BY: D.E.G.
SHEET 51 OF 245

FILE NAME = V:\Projects\ANY\K2\20615\CADD\MSTN\08_@96\consultants\208_@96tss1.dgn
DATE/TIME = 6/30/2014
USER = 4916