



NOTES:

1. THE CONTRACTOR IS NOTIFIED THAT NO TEMPORARY CAUSEWAY HAS BEEN PERMITTED IN THE IMMEDIATE VICINITY OF THE EXISTING BRIDGE; THE SUBSTRUCTURE REMOVAL SCHEME SHOULD BE DEVELOPED ACCORDINGLY.
2. SAW CUT EXISTING SUBSTRUCTURES 3" DEEP ALONG CUT LINES PRIOR TO BEGINNING CONCRETE REMOVAL OPERATIONS.

LEGEND



EXISTING STRUCTURE TO BE COMPLETELY REMOVED UNDER ITEM 529.25 REMOVAL OF CONCRETE OR MASONRY



SUBSTRUCTURE REMOVAL DETAILS

| | |
|-------------------------------|----------------------|
| PROJECT NAME: RUTLAND CITY | PLOT DATE: 6/30/2014 |
| PROJECT NUMBER: BRP 3000 (19) | DRAWN BY: D.M.D. |
| PROJECT LEADER: M.D.S. | CHECKED BY: P.M.P. |
| DESIGNED BY: D.M.D. | DWG. NO.: |
| | SHEET 70 OF 245 |

FILE NAME = V:\P\c\seas\ANY\K2\2015\CADD\WSTN\08\096\ecmsul\anta\208\096\substructure\removal.dgn
DATE/TIME = 6/30/2014
USER = 4916