

# QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
					ROADWAY	TRAINING	EROSION CONTROL	UTILITIES - BID ITEMS	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					0.5						0.5		LS	MOBILIZATION/DEMobilIZATION	635.11				
					3070						3070		LF	DURABLE 4 INCH WHITE LINE, RECESSED POLYUREA	646.406				
					3380						3380		LF	DURABLE 4 INCH YELLOW LINE, RECESSED POLYUREA	646.416				
					51						51		LF	DURABLE 24 INCH STOP BAR, RECESSED TYPE A TAPE	646.4871				
					3070						3070		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602				
					3380						3380		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612				
									3250		3250		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							200				200		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							179				179		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
							1022				1022		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							130				130		LB	SEED	651.15				
							100				100		LB	SEED, WINTER RYE	651.17				
							800				800		LB	FERTILIZER	651.18				
							3				3		TON	AGRICULTURAL LIMESTONE	651.20				
							3				3		TON	HAY MULCH	651.25				
							820				820		CY	TOPSOIL	651.35				
									1390		1390		SY	GRUBBING MATERIAL	651.40				
							1				1		LS	EPSC PLAN (BR 2)	652.10				
							350				350		HR	MONITORING EPSC PLAN	652.20				
							1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BR 2)	652.30				
							1650				1650		SY	TEMPORARY EROSION MATTING	653.20				
							112				112		CY	VEHICLE TRACKING PAD	653.35				
							1110				1110		LF	BARRIER FENCE	653.50				
							1429				1429		LF	PROJECT DEMARCATION FENCE	653.55				
					12						12		EACH	DECIDUOUS TREES (ACER SACCHARUM, 2 1/2" - 3" CAL.)	656.30				
					80						80		SF	TRAFFIC SIGNS, TYPE A	675.20				
					100						100		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
					22						22		EACH	REMOVING SIGNS	675.50				
					154						154		LF	WIRED CONDUIT (2")	678.23				
					1						1		EACH	POWER DROP STANCHION, STREET LIGHTING	679.55				
					1						1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
							2				2		EACH	SPECIAL PROVISION (6" SWING CHECK VALVE)	900.620				
					12						12		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620				
					4						4		EACH	SPECIAL PROVISION (GUARDRAIL APPROACH SECTION TO CONCRETE COMBINATION BRIDGE RAILING)	900.620				
							5				5		EACH	SPECIAL PROVISION (SANITARY MANHOLE, ALL-INCLUSIVE) (4' DIA.)	900.620				
									556		556		LF	SPECIAL PROVISION (BRIDGE RAILING TEXAS) (FPQ)	900.640				
							60				60		LF	SPECIAL PROVISION (C-900 PVC, ALL-INCLUSIVE) (12" SEWER OVERFLOW)	900.640				
									89		89		LF	SPECIAL PROVISION (DRILLED SHAFT IN EARTH) (8 FT)	900.640				
									10		10		LF	SPECIAL PROVISION (DRILLED SHAFT OBSTRUCTION DRILLING AND REMOVAL)	900.640				

PROJECT NAME: RUTLAND CITY  
 PROJECT NUMBER: BRF 3000 (16)  
 FILE NAME: s94j092qty.dgn PLOT DATE: 14-JUL-2014  
 PROJECT LEADER: C. CARLSON DRAWN BY: G. ROY  
 DESIGNED BY: M. EVANS-MONGEON CHECKED BY: EVANS-MONGEON  
 QUANTITY SHEET 3 SHEET 129 OF 245