

# QUANTITY SHEET 4

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
					ROADWAY	TRAINING	EROSION CONTROL	UTILITIES - BID ITEMS	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								203			203		LF	SPECIAL PROVISION (DUCTILE IRON PIPE, CEMENT LINED, ALL-INCLUSIVE) (6" FORCE MAIN)	900.640				
								330			330		LF	SPECIAL PROVISION (DUCTILE IRON PIPE, CEMENT-LINED, ALL-INCLUSIVE)(10" SEWER)	900.640				
								54			54		LF	SPECIAL PROVISION (DUCTILE IRON PIPE, CEMENT-LINED, ALL-INCLUSIVE)(10" WATER INSULATED IN CASING)	900.640				
								268.4			268.4		LF	SPECIAL PROVISION (DUCTILE IRON PIPE, CEMENT-LINED, ALL-INCLUSIVE)(10" WATER INSULATED ON BRIDGE )	900.640				
								1300			1300		LF	SPECIAL PROVISION (DUCTILE IRON PIPE, CEMENT-LINED, ALL-INCLUSIVE)(10" WATER)	900.640				
								30			30		LF	SPECIAL PROVISION (DUCTILE IRON PIPE, CEMENT-LINED, ALL-INCLUSIVE)(6" WATER)	900.640				
								50			50		LF	SPECIAL PROVISION (DUCTILE IRON PIPE, CEMENT-LINED, ALL-INCLUSIVE) (6" FORCE MAIN IN CASING)	900.640				
								272			272		LF	SPECIAL PROVISION (DUCTILE IRON PIPE, CEMENT-LINED, ALL-INCLUSIVE) (6" FORCE MAIN ON BRIDGE)	900.640				
								790			790		LF	SPECIAL PROVISION (SDR-35 PVC, ALL-INCLUSIVE) (10" SEWER)	900.640				
								35			35		LF	SPECIAL PROVISION (SDR-35 PVC, ALL-INCLUSIVE) (6" SEWER SERVICE)	900.640				
								60			60		LF	SPECIAL PROVISION (SEAMLESS COPPER WATER TUBE, ALL-INCLUSIVE) (1" SERVICE)	900.640				
								25			25		LF	SPECIAL PROVISION (SEAMLESS COPPER WATER TUBE, ALL-INCLUSIVE) (2" SERVICE)	900.640				
								475			475		LF	SPECIAL PROVISION (TRANSITE PIPE REMOVAL)	900.640				
								1			1		LS	SPECIAL PROVISION (EMERGENCY BACKUP PORT)	900.645				
								1			1		LS	SPECIAL PROVISION (FLAPPER VALVE AND HEADWALL)	900.645				
					1						1		LS	SPECIAL PROVISION (GATE FOR ORNAMENTAL FENCE, 4 FEET)	900.645				
									1		1		LS	SPECIAL PROVISION (MOBILIZATION OF DRILLED SHAFT EQUIPMENT)	900.645				
								1			1		LS	SPECIAL PROVISION (PUMP STATION MODIFICATIONS)	900.645				
									1		1		LS	SPECIAL PROVISION (QC/QA CLEANING AND PAINTING STRUCTURAL COMPONENTS)	900.645				
					1						1		LS	SPECIAL PROVISION (TEMPORARY CAUSEWAY) (BR 2)	900.645				
					1						1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) (BR 2)	900.645				
					100						100		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675				
					36				4		40		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683				

PROJECT NAME: RUTLAND CITY  
 PROJECT NUMBER: BRF 3000 (16)  
 FILE NAME: s94j092qty.dgn PLOT DATE: 14-JUL-2014  
 PROJECT LEADER: C. CARLSON DRAWN BY: G. ROY  
 DESIGNED BY: M. EVANS-MONGEON CHECKED BY: EVANS-MONGEON  
 QUANTITY SHEET 4 SHEET 130 OF 245