STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																					REMARKS		SIGN DETAIL	
		EACH	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POST	FLANGED CHANNEL (LB / FT)			SQUARE STEEL (in) (LB / FT)			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) (LB / FT)			FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT)				W-SHAPE STEEL (LB / FT)				SIGN FRAME REQUIRED	SHSM = FHWASTANDARD HIGHWAY SIGNS AND MARKINGS BOOK	DETAIL IN SHSM	DETAIL ON DWG NUMBER	STANDARD SHEET NUMBER
															1.75	2.00	2.50			3.00	4.00	4.0 MOD		3.00	3.50	4.00	5.00	FTG. SIZE								
												1.12	2.00	3.00	1.88	2.42	3.35			1.30	1.70	1.70		7.60	9.00	10.80	14.60	24"	30"							
(TH10) STA 500+20	Dorr Dr	1	36.0	12.0	3.00						1					X		X														D3-1		TRAFFIC SIGN DETAIL SHEET	
	River St	1	36.0	12.0	3.00																											D3-1		TRAFFIC SIGN DETAIL SHEET	
	STOP	1	30.0	30.0	6.25																											R1-1	X		
	ALL WAY	1	18.0	6.0	0.75																											R1-4	X		
(TH10) STA 502+25	BIKE ROUTE	1	24.0	18.0	3.00						1					X		X														D11-1	X		
	College	1	24.0	6.0	1.00																											D1-1 (MOD.)		TRAFFIC SIGN DETAIL SHEET	
	School St	1	24.0	6.0	1.00																											D1-1 (MOD.)		TRAFFIC SIGN DETAIL SHEET	
(TH10) STA 503+25		1	36.0	36.0	9.00						2					X		X														W1-10	X		
(TH8) STA 100+30	BRIDGES FREEZE BEFORE ROAD	1	30.0	30.0	6.25						1					X		X														VW-005			E-150
(TH8) STA 106+30	NO PARKING THIS SIDE	1	18.0	24.0	3.00						1					X		X														R8-3	X		
	BRIDGES FREEZE BEFORE ROAD	1	18.0	30.0	3.75																											VW-005			E-150
	SUB-TOTALS THIS SHEET				40.00											42.5		5.0																	
	PROJECT TOTALS				79.25											99.0		11.0																	
	ROUNDING				0.75											1.0		0.0																	
												FT .	FT .	FT .	FT	FT 100.	FT .	XXXXX XXXXX XXXXX XXXXX XXXXX	EA	LB .	LB .	LB .		LB .	LB .	LB .	LB .							
	TOTALS				SF 80.	SF .	EA. .	SF .	XXXXXXXXXX XXXXXXXXXX XXXXXXXXXX			FT .			FT 100.				LB .				EA.	LB .				EA. .	EA. .	LB .						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: BRF 3000 (16)

FILE NAME: s94j092tss.dgn
PROJECT LEADER: C. CARLSON
DESIGNED BY: M.EVANS-MONGEON
TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 03-JUL-2014
DRAWN BY: C. MOONEY
CHECKED BY: EVANS-MONGEON
SHEET 150 OF 245