



- NO EXCEPTION TAKEN
- MAKE CORRECTIONS NOTED
- REJECTED
- REVISE AND RESUBMIT
- SUBMIT SPECIFIED ITEM

CHECKING IS ONLY FOR THE GENERAL CONFORMANCE WITH THE DESIGN CONCEPT OF THE PROJECT AND GENERAL COMPLIANCE WITH THE INFORMATION GIVEN IN THE CONTRACT DOCUMENTS. ANY ACTION SHOWN IS SUBJECT TO THE REQUIREMENTS OF THE PLANS AND SPECIFICATIONS. CONTRACTOR IS RESPONSIBLE FOR DIMENSIONS WHICH SHALL BE CONFIRMED AND CORRELATED AT THE JOB SITE; FABRICATION PROCESSES AND TECHNIQUES OF CONSTRUCTION; COORDINATION OF HIS WORK WITH THAT OF ALL OTHER TRADES AND THE SATISFACTORY PERFORMANCE OF THE WORK.

CHA
 DATE 4-15-2016 BY Jeff Najdowski

TEMP. SETTING CHART		
TEMP °F	DIM "A"	DIM "B"
0	2 3/8"	5 3/8"
15°	1 7/8"	4 7/8"
30°	1 5/8"	4 5/8"
45°	1 7/16"	4 7/16"
60°	1 3/16"	4 3/16"
75°	1 5/16"	3 11/16"
90°	1 1/16"	3 11/16"
105°	1/2"	3 1/2"

Vermont Agency of Transportation
RECEIVED
 ON: **April 12, 2016**
 and Checked for
CONFORMANCE
 BY: **ABC** DATE:

1	4/07/16	REVISION PER APPROVAL	SLB	JEB		
REV.	DATE	REMARKS	DWN	CHK	APVL	SHOP
MATERIAL:		SURFACE PREP. & PAINT:		HOLES:		SHOP BOLTS:
M270M-250 U.N.O.		GALV. - PER STD. 726.08		AS NOTED		AS NOTED
DESCRIPTION: EXPANION JOINT - FABRICATION SHEET						
CASCO BAY STEEL STRUCTURES, INC.						
1 WALLACE AVE.			PHONE (207) 780-6722			
SOUTH PORTLAND, ME 04106			FAX. (207) 780-6726			
STRUCTURE: BRIDGE NO. 17				DRAWN:	DATE:	
TH 10 (RIPLEY ROAD) OVER OTTER CREEK				SLB	03/23/16	
STATE OF VERMONT AGENCY OF TRANS.				CHKD:	DATE:	
				JEB	03/23/16	
LOCATION: RUTLAND CITY, VT			JOB NO.	DWG NO.		
PROJ NO. BRF 3000(19)			598	E101		
CUSTOMER: KUBRICKY CONSTRUCTION CORP.				REV. 1		

NOTES:
 - ALL DIMENSIONS SHOWN HORIZONTAL U.N.O.
 - ALL DIMENSIONS SHOWN AT 45°.