

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EC	RAILROAD	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
								292			292		CY	UNCLASSIFIED EXCAVATION	203.17	0.59			
								125			125		CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	1.11			
								691			691		CY	EARTH BORROW	203.30				
								167			167		CY	SAND BORROW	203.31	0.78			
								80			80		CY	TRENCH EXCAVATION OF EARTH	204.20	0.04			
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								562			562		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	5.06			
								9			9		CY	AGGREGATE SURFACE COURSE	401.10	0.08			
								1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								970			970		LB	REINFORCING STEEL, LEVEL I	507.11	8.88			
								324			324		LF	JOINT SEALER, HOT Poured	524.11	3			
								16.8			16.8		CY	CONCRETE, CLASS B	541.25	0.13			
								28			28		LF	12" CSP .064 (2-2/3 X 1/2)	601.0005	0.07			
								44			44		LF	18" RCP CLASS IV	601.0816	0.31			
								1			1		EACH	18" RCPEs CLASS III	601.6815				
								1			1		EACH	PRECAST REINFORCED CONCRETE MANHOLE WITH CAST IRON COVER	604.21				
								9			9		MGAL	DUST CONTROL WITH WATER	609.10	0.07			
								1.1			1.1		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	0.002			
								1.45			1.45		CY	STONE FILL, TYPE II	613.11	0.01			
								15			15		LF	VERTICAL GRANITE CURB	616.21				
								15			15		LF	REMOVAL OF EXISTING CURB	616.41				
								1			1		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10				
								7.5			7.5		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10				
								16			16		SF	DETECTABLE WARNING SURFACE	618.30				
								2			2		EACH	STEEL MARKER POSTS	619.16				
								161			161		LF	SEAMLESS COPPER WATER TUBE (1 INCH DIA.)	629.23				
								1			1		EACH	EXTENSION SERVICE BOX AND CURB STOP (1 INCH DIA.)	629.25				
								150			150		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
								540			540		HR	FLAGGERS	630.15				
								1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
								1200			1200		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	10			
								24			24		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482				
								103			103		LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502				
								3			3		EACH	DURABLE RAILROAD CROSSING SYMBOL, THERMOPLASTIC	646.512				
								915			915		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	1.02			
									186		186		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	0.67			
									16		16		LB	SEED	651.15	0.7			
									96		96		LB	FERTILIZER	651.18	0.38			
									0.21		0.21		TON	AGRICULTURAL LIMESTONE	651.20				

PROJECT NAME: ARLINGTON
PROJECT NUMBER: STP 0114 (4)
FILE NAME: Z09G0520S.DGN
PROJECT LEADER: J.READ
DESIGNED BY: LB
QUANTITY SHEET #1
PLOT DATE: 2/22/2016
DRAWN BY: LB
CHECKED BY: ABR
SHEET 3 OF 27