

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES				TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	BRIDGE	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
385			385		CY	COMMON EXCAVATION	203.15				
9			9		CY	SOLID ROCK EXCAVATION	203.15				
1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.1)	204.22				
	13		13		CY	STRUCTURE EXCAVATION	204.25				
	12		12		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
58			58		SY	COLD PLANNING BITUMINOUS PAVEMENT	210.10				
300			300		CY	SUBBASE OF GRAVEL	301.15				
1			1		CY	AGGREGATE SHOULDERS, IN PLACE	402.10				
2			2		CWT	EMULSIFIED ASPHALT	404.65				
121			121		TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.25				
1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.1)	406.50				
	110		110		CY	CONCRETE, HIGH PERFORMANCE CLASS AA	501.32				
	25		25		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
	1		1		LS	SHORING SUPERSTRUCTURE	502.10				
	183254		183254		LB	STRUCTURAL STEEL, ROLLED BEAM	506.50				
	3200		3200		LB	STRUCTURAL STEEL	506.60				
	3200		3200		LB	REINFORCING STEEL	507.15				
	280		280		LF	DRILLING AND GROUTING DOWELS	507.16				
	19000		19000		LB	EPOLYCOATED REINFORCING STEEL	507.17				
	1		1		LS	SHEAR CONNECTORS (250-1/2" x 2")	508.15				
	1		1		LS	SHEAR CONNECTORS (3366-7/8" x 6")	508.15				
	1		1		LS	STRUCTURAL PAINTING, FIELD APPLIED	513.30				
	1		1		LS	CONTAMINANT & ENVIRONMENTAL PROTECTION FIELD	513.36				
	1		1		LS	SURFACE PREPARATION, FIELD	513.41				
	110		110		GAL	WATER REPELLENT, SILANE	514.10				
	22		22		LF	BRIDGE EXPANSION JOINT, VERMONT	515.11				
	1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	520.20				
	30		30		CY	REMOVAL OF CONCRETE OR MASONRY	520.25				
24			24		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE 1	605.25				
1			1		MSAL	DUST CONTROL WITH WATER	609.10				
	6		6		CY	STONE FILL, TYPE 1	613.10				
110			110		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	618.28				
56			56		LF	REMOVAL OF EXISTING CURB	618.41				
65			65		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10				
2			2		EACH	REMOVING AND RESETTING PROPERTY MARKERS	619.20				
200			200		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.60				
300			300		HR	FLAGGERS	630.15				
		1	1		LS	FIELD OFFICE ENGINEERS	631.10				
		1	1		LS	TESTING EQUIPMENT, CONCRETE	631.15				

