STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - ENOSBURG

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
							BOSTON POST ROAD																						
EB	MM 0.003, RT	A	W3-1	36	36			9.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS ACROSS FROM POLE# 37 AND 15 FT EAST	X		
WB	MM 0.027, LT	F	R2-1	24	30			5.00								1		X								INSTALL NEW SIGN AND POST 48 FT WEST OF POLE# 2	X		
EB	MM 0.099, RT	A	R1-1	30	30			6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
EB	MM 0.100, RT	A/B	D3-1	54	12			4.50					X			2		X								INSTALL NEW SIGN ON 2-POSTS 5' SOUTH OF STOP SIGN. INSTALL SIGN AS NOT TO OBSTRUCT VIEW OF STOP SIGN		8	
		C/D	D3-1	54	12			4.50					X													INSTALL NEW SIGN ABOVE BOSTON POST RD SIGN ON SAME POSTS		8	
WB	MM 0.099, LT	F	R1-1	30	30			6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
WB	MM 0.115, RT	F	R1-1	30	30			6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
WB	MM 0.116, RT	A/B	D3-1	54	12			4.50					X			2		X								INSTALL NEW SIGN ON 2-POSTS 5' NORTH OF STOP SIGN. INSTALL SIGN A AS NOT TO OBSTRUCT VIEW OF STOP SIGN		8	
		C/D	D3-1	54	12			4.50					X													REMOVE SIGN AND INSTALL ABOVE NEW BOSTON POST RD STREET NAME SIGN		8	
EB	MM 0.176, LT	A	R2-1	24	30			~~5.00~~								~~1~~		~~X~~								INSTALL NEW SIGN AND POST 37 FT WEST OF POLE# 3	X		
WB	MM 0.207, RT	F	W3-1	36	36			9.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS ACROSS FROM POLE# 4 AND 48 FT WEST	X		
							TYLER BRANCH ROAD																						
NB	MM 0.053, RT	A	W2-1	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 97 FT SOUTH OF POLE# 170/146	X		
		A	W16-8P	42	8			~~2.33~~ 2.749																		INSTALL NEW SIGN BENEATH INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
NB	MM 0.094, RT	A	W20-1	36	18								X		X											REMOVE SIGN AND POST			
										EA	EA	EA	EA 10	EA	EA 6		FT	FT 210	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF ~~73.33~~ 68.749	SF	EA 10				EA ~~6~~		EA ~~14~~	FT 210			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
ENOSBURG TRAFFIC SIGN SUMMARY SHEET 1
PLOT DATE: 14-SEP-2012 15:28
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 12 OF 51