STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - ENOSBURG

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.095, RT	A	W5-3	36	36		ONE LANE BRIDGE	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 23 FT SOUTH OF POLE# 4/145	X		
SB	MM 0.103, LT	F	G20-2	36	18		END ROAD WORK						X		X											REMOVE SIGN AND POST			
NB	MM 0.134, RT	A	TOWN SIGN	30	30		ONE LANE ROAD AHEAD						X		X											REMOVE SIGN AND POST			
		A	W3-2	36	36			9.00								2		X								INSTALL NEW SIGN AND POST 32 FT NORTH OF POLE# 144	X		
SB	MM 0.168, LT	F	R2-1	24	30		SPEED LIMIT 50	5.00								1		X								INSTALL NEW SIGN AND POST ACROSS FROM POLE# 16/143/E51	X		
NB	MM 0.200, LT	A	R1-2	36	36		YIELD	3.89					X		X	1		X								INSTALL NEW SIGN AND POST 4 FT NORTH OF POLE# 66/4/142	X		
		A	R1-2AP	24	18		TO ONCOMING TRAFFIC	3.00																		INSTALL NEW SIGN BENEATH YIELD SIGN ON SAME POST AT CORRECT SIGN HEIGHT	X		
NB	MM 0.204, LT	A	R1-2	36	36		YIELD						X		X											REMOVE SIGN AND POST			
NB	MM 0.237, RT	A	OM3-R	12	36			3.00					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AT SOUTHEAST END OF BRIDGE FACING SOUTH	X		
SB	MM 0.237, LT	E	OM3-L	12	36			3.00					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AT SOUTHWEST END OF BRIDGE FACING SOUTH	X		
NB	MM 0.250, RT	B	OM3-L	12	36			3.00					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AT NORTHEAST END OF BRIDGE FACING NORTH	X		
SB	MM 0.250, LT	F	OM3-R	12	36			3.00					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AT NORTHWEST END OF BRIDGE FACING NORTH	X		
NB	MM 0.284, RT	A	R2-1	24	30		SPEED LIMIT 50	5.00								1		X								INSTALL NEW SIGN AND POST 180 FT NORTH OF THE NORTH END OF THE BRIDGE	X		
SB	MM 0.284, LT	F	R1-2	36	36		YIELD						X		X											REMOVE SIGN AND POST			
		F	R1-2AP	24	18		TO ONCOMING TRAFFIC						X													REMOVE SIGN			
SB	MM 0.302, LT	F	W5-3	36	36		ONE LANE BRIDGE	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 290 FT SOUTH OF POLE# 3	X		
										EA	EA	EA	EA 10	EA	EA 9			FT 195						LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 55.89	SF	EA 10				EA ~~9~~		EA ~~13~~		FT 195		EA	LB										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
ENOSBURG TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 14-SEP-2012 15:29
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 13 OF 51