STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 – FERRISBURGH

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
EB	MM 1.600, RT	A/B	D3-1	36	12		Walker Rd	3.00					X													INSTALL SIGN ABOVE STOP WITH UPDATED DESIGN		9	
		A	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
WB	MM 1.603, LT	E/F	D3-1	30	6		Walker Rd						X		X											REMOVE SIGN AND POST			
EB	MM 1.707, RT	A	W2-2 R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 296 FT WEST OF POLE# 103814/15/2-13/15	X		
		A	W16-8P	30	8		Walker Rd	1.67																		INSTALL BENEATH SIDE ROAD WARNING SIGN AT THE CORRECT SIGN HEIGHT		9	
EB	MM 1.919, RT	B	W1-6 R	48	24			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 1167 FT WEST OF POLE# 103815/15-50/15 1/2 AT RIGHT ANGLES TO APPROACHING TRAFFIC	X		
EB	MM 1.928, LT	C	W1-6 L	48	24			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 1214 FT WEST OF POLE# 103815/15-50/15 1/2 AT RIGHT ANGLES TO APPROACHING TRAFFIC	X		
WB	MM 2.625, LT	F	W5-2	36	36		NARROW BRIDGE	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 232 FT EAST OF AND ACROSS FROM POLE# 103833/31/31	X		
WB	MM 2.676, LT	F	OM3-R	12	36			3.00								1		X								INSTALL OBJECT MARKER AT THE EAST END OF THE BRIDGE ON THE NORTHEAST (LEFT) CORNER - 37 FT WEST OF AND ACROSS FROM POLE# 103833/31/31	X		
EB	MM 2.676, RT	B	OM3-L	12	36			3.00								1		X								INSTALL OBJECT MARKER AT THE EAST END OF THE BRIDGE ON THE SOUTHEAST (RIGHT) CORNER - 1172FT WEST OF POLE# 2/36 AND POLE# 111204/15/11	X		
WB	MM 2.692, LT	E	OM3-L	12	36			3.00								1		X								INSTALL OBJECT MARKER AT THE WEST END OF THE BRIDGE ON THE NORTHWEST (LEFT) CORNER - 121FT WEST OF AND ACROSS FROM POLE# 103833/31/31	X		
EB	MM 2.692, RT	A	OM3-R	12	36			3.00								1		X								INSTALL OBJECT MARKER AT THE WEST END OF THE BRIDGE ON THE SOUTHWEST (RIGHT) CORNER - 121FT WEST OF POLE# 103833/31/31	X		
WB	MM 2.625, LT	F	W5-2	36	36		NARROW BRIDGE	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 69 FT EAST OF AND ACROSS FROM POLE# 04872/33	X		
WB	MM 3.287, LT	F	W1-2 L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 121FT WEST OF POLE# 103844/39-50/39 1/2 AND 25 FT WEST OF THE CENTER OF THE FIELD DRIVE	X		
EB	MM 3.398, RT	A	W1-2 R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 20 FT FT WEST OF POLE# 103847/41/41	X		
										EA	EA	EA	EA 3	EA	EA 2		FT	FT 240	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 75.67	SF	EA 3				EA ~~2~~		EA ~~16~~	FT 240			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PLOT DATE: 14-SEP-2012 15:29
PROJECT LEADER: JLS
DRAWN BY: ITS
DESIGNED BY: NLA
CHECKED BY: JLS
FERRISBURGH TRAFFIC SIGN SUMMARY SHEET 4
SHEET 20 OF 51